

COLLIN COUNTY

SUBDIVISION REGULATIONS

Approved by the Collin County Commissioners Court on: October 5, 2026

Court Order Number: 2026-1138-10-05

TABLE OF CONTENTS

1.01	INTRODUCTION.....	5
A.	General Provisions.....	5
B.	Findings.....	5
C.	Order.....	6
D.	Applicable Jurisdiction.....	6
E.	Interpretation.....	6
F.	Applicability.....	6
G.	Delegation of Authority to the Director of Engineering as Designee of the Commissioners Court.....	7
H.	Exceptions from Plat Requirements.....	8
I.	Process for Exceptions from Platting Requirements.....	10
J.	Version of Regulations Applicable.....	10
K.	Required Permits.....	10
L.	Appendices Incorporated.....	10
M.	Subdivision Development Process.....	10
1.02	DEFINITIONS	13
A.	Definitions	13
1.03	PLAT PACKAGE SUBMISSION	19
A.	Process Overview	19
B.	Administrative Completeness	19
C.	Street Sign Plan.....	20
D.	Application Fees	20
E.	Final Plat Package Requirements	20
F.	Requirements For Final Plats.....	22
G.	Amending Plat, Replat or Plat Revision, Minor Plat, Cancellation	24
1.04	DECISIONS ON THE PLAT PACKAGE	26
A.	Submission to the Commissioners Court and Post-Submission Process.....	26
B.	Effect Of Approval	28
C.	Securing Completion of Road and Drainage Infrastructure Improvements.....	28
D.	Compliance with Subdivision Rules.....	30
E.	Recording of Plat	30
F.	No New Road or Drainage Infrastructure Improvements	31
G.	Approval Expiration	31
1.05	SUBDIVISION RULES	32
A.	Lots	32
B.	Roadways.....	32

C.	Drainage	32
D.	Floodplain	32
E.	Design Requirements for Utilities.....	33
F.	Shared Access Driveways	33
G.	Mailboxes	33
H.	Signs.....	34
1.06	CONSTRUCTION PLAN SUBMISSION AND REVIEW	34
A.	General	34
B.	General Civil Construction Plan Requirements	34
C.	Civil Construction Plan Checklist	36
1.07	GENERAL CONSTRUCTION REQUIREMENTS	40
A.	General	40
B.	Construction Sequencing.....	41
C.	Temporary Traffic Control	42
D.	“Accepted” as Used Herein	43
E.	Compliance with Subdivision Rules	43
1.08	ACCEPTANCE OF CONSTRUCTION AS COMPLETE	43
A.	“Accepted” as Used Herein	43
B.	Applicant or Contractor Request for Inspection	43
C.	Post-Inspection.....	43
1.09	WARRANTY AND SECURING MAINTENANCE OBLIGATION	44
A.	Required For Acceptance As Complete	44
B.	Nature Of Warranty.....	44
C.	Warranty Period	44
D.	Bond For Maintenance During Warranty Period.....	44
E.	Maintenance During the Warranty Period.....	45
F.	Provision For Maintenance of Drainage Improvements	46
1.10	ACCEPTANCE OF ROADWAYS FOR COUNTY MAINTENANCE	46
A.	Identified Defects and Deficiencies Must be Remedied	46
B.	Roadways Not Eligible for County Maintenance.....	47
1.11	PRIVATE ROADS	47
A.	Compliance with these Subdivision Regulations.....	47
B.	Bonds or Other Financial Assurances	48
C.	Plat Notes Regarding Private Roads	48
D.	Development Along Existing Private Roads.....	48

1.12	VARIANCE	48
A.	Criteria for Variances.....	48
B.	Application Materials	49
C.	Grant or Denial of Variance	49
1.13	ENFORCEMENT; PENALTIES; APPEALS; CONFLICT OF INTEREST; SEVERABILITY	49
A.	Category of Offense.....	49
B.	Enforcement Actions	49
C.	Enforcement of Plat Notes	49
D.	Conflict of Interest.....	49
E.	Severability	50
F.	Amendment to Regulations.....	50
G.	Appeal.....	50
	APPENDIX A OWNER AUTHORIZATION FORM	51
	APPENDIX B CERTIFICATIONS.....	52
	APPENDIX C STANDARD PLAT NOTES	58
	APPENDIX D SPECIAL PLAT NOTES FOR PRIVATE ROADS AND SHARED ACCESS DRIVEWAYS.....	60
	APPENDIX E STANDARD PLAT NOTES FOR SPECIAL DISTRICTS	61
	APPENDIX F CONSTRUCTION PLAN NOTES	63
	APPENDIX G SAMPLE PERFORMANCE BOND	69
	APPENDIX H SAMPLE MAINTENANCE BOND.....	72
	APPENDIX I SAMPLE WARRANTY LETTER.....	75

COLLIN COUNTY SUBDIVISION REGULATIONS

1.01 INTRODUCTION

A. General Provisions

These Subdivision Regulations have been adopted to encourage the orderly and efficient development of rural and suburban areas within Collin County by establishing standards for the provision of adequate sanitation, stormwater drainage, floodplain management, transportation infrastructure, public utilities and facilities, and other features that are necessary for ensuring the creation and continuance of a healthy, attractive, safe and efficient community that provides for the conservation, enhancement and protection of its human and natural resources. These Regulations have been prepared to promote the health, safety and general welfare of the citizens of Collin County.

B. Findings

The Collin County Commissioners Court hereby makes the following findings:

1. The Commissioners Court has been delegated the authority to regulate the subdivision and development process pursuant to Chapter 232. Local Government Code;
2. The Commissioners Court has been designated by the Texas Commission on Environmental Quality (TCEQ) as the authorized agent for the licensing and regulation of on-site sewage facilities (OSSFs) within Collin County, and these Regulations are a necessary component of such regulation;
3. The Commissioners Court has been granted authority and responsibility under the Texas Health and Safety Code, Chapter 366, to regulate the use of OSSFs within Collin County. The Commissioners Court has considered the potential pollution, nuisances and injury to public health that could be caused by the use of private sewage facilities within Collin County, and has adopted rules and regulations for OSSFs (reference Court Order 2008-187-03-11) to abate or prevent the potential pollution, nuisances or injury to public health;
4. The Commissioners Court has been granted authority and responsibility under the National Flood Insurance Program, 44 CFR, and Chapter 16, Section 16.315, Water Code, to administer floodplain development regulations within Collin County, and has adopted and will administer the most recent version of the Collin County Floodplain Management Regulations to regulate associated development;
5. The Commissioners Court has the authority and obligation to exercise general control over the roadways, highways, bridges and related drainage structures and development within Collin County, and therefore has adopted and will administer the most recent Collin County Drainage Design Standards, Collin County Roadway Standards, and these Regulations as a necessary component of such obligations;
6. The Commissioners Court has the authority and obligation to protect the public health, safety and welfare of the citizens of Collin County;
7. The Commissioners Court has considered the potential burden upon landowners and taxpayers of substandard development, sanitary facilities, drainage, floodplain management, and/or roadway construction; and,
8. These Regulations are adopted to preserve and protect the resources, public

health and private property interests within Collin County.

C. Order

The Commissioners Court of Collin County, following public notice, investigation and hearing, has declared these Subdivision Regulations to be necessary and appropriate to accomplish the purposes and goals stated above. These Regulations have been adopted by order of the Collin County Commissioners Court 2020-957-09-28 to provide a model for the orderly and efficient development of the rural and suburban areas within Collin County.

D. Applicable Jurisdiction

These Regulations apply to areas within Collin County that are located outside of the corporate limits of a municipality. Additionally, these Regulations shall exclude areas within Collin County that are located within the extraterritorial jurisdiction (ETJ) of a municipality, provided that an ETJ has been established by the municipality and the municipality has entered into a written interlocal agreement with the County that identifies the municipality as the entity authorized to regulate plats within their respective ETJ, in accordance with Section 242, Local Government Code.

E. Interpretation

In the interpretation and application of the provisions of these Regulations, it is the intention of the Commissioners Court that the principles, standards and requirements provided for herein shall be minimum requirements for the platting and developing of subdivisions within Collin County and shall supersede any previous Subdivision Regulation in their entirety. Furthermore, it is the intent of the Commissioners Court that these Regulations shall be interpreted in conjunction with the Court's orders relating to on-site sewage facilities, drainage design, floodplain development, and roadway standards.

F. Applicability

1. Upon adoption of these Regulations, the owner of a tract of land located outside the limits of a municipality must have a plat of the subdivision prepared, unless exempt in accordance with Section 1.01 H or if the Applicant has a vested right to have the Applicant's submission governed by the prior version of these Regulations in accordance with Section 1.01 J, if the owner divides the tract into 2 or more parts to lay out:
 - a. a subdivision of the tract, including an addition;
 - b. lots; or
 - c. streets, alleys, squares, parks, or other parts of the tract intended by the owner of the tract to be dedicated to public use.

A division of a tract includes a division regardless of whether it is made by using a metes and bounds description in a deed of conveyance or in a contract for a deed, by using a contract of sale or other executory contract to convey, or by using any other method. The development of Recreational Vehicle Parks and Single-Family Rental Developments shall be subject to the platting requirements of these Regulations regardless of whether individual lots are intended to be sold or retained under common ownership.

2. Subdivision in the ETJ of a Municipality
 - d. A Municipality's authority to regulate Subdivisions includes its ETJ. Properties in the ETJ of a city may or may not be governed by these Regulations.
 - e. If the Applicant has land within the ETJ of a city, the Applicant shall contact the city that established the ETJ to determine if the city has entered into a written interlocal agreement (ILA) with the County that identifies the city as the entity authorized to regulate plats within their ETJ, in accordance with Section 242.001, Local Government Code. If the city has an approved ILA with the County, then the Plat shall be processed through the City.
 - f. Even if a Plat is processed through a city, the Applicant shall submit the OSSF Suitability Plat Review application to the Collin County Development Services Department.
 - g. An Applicant seeking to construct roadways in a city's ETJ, that are intended to be dedicated for public maintenance, shall comply with the requirements of the city and these Regulations, whichever is more stringent. At a minimum, roadways in a city's ETJ shall adhere to the design, civil construction plan, construction, testing, inspection, and bonding requirements described throughout these Regulations and the Collin County Roadway Standards. The Applicant shall contact the Collin County Engineering Department for more details on the County's involvement in the infrastructure construction and acceptance process.
3. Future Transportation Corridors
 - a. If all or part of a Subdivision for which a Plat is required is located within a Future Transportation Corridor identified in an agreement under Section 201.619, Transportation Code, the Commissioners Court may:
 - i. refuse to approve the Plat for recordation unless the Plat states that the Subdivision is located within the area of the alignment of a transportation project as shown in the final environmental decision document that is applicable to the Future Transportation Corridor; and
 - ii. refuse to approve the Plat for recordation if all or part of the Subdivision is located within the area of the alignment of a transportation project as shown in the final environmental decision document that is applicable to the Future Transportation Corridor.
 - b. The Commissioners Court or their designee may refuse to review a plat application or refuse to approve a plat for recordation for failure to identify a corridor, as identified by Section 201.619, Transportation Code, if the corridor is part of an agreement between the Texas Department of Transportation and the County under that section.
- G. Delegation of Authority to the Director of Engineering as Designee of the Commissioners Court

In addition to other authorities expressly delegated to the Director of Engineering elsewhere in these Regulations, the Director of Engineering or their designee is designated and authorized by the Collin County Commissioners Court to:

1. Receive all Plat Package Submissions;
 2. Determine whether each Plat Package Submission is complete;
 3. Compile and issue a list of documentation and other information that must be submitted with the Plat Package in order for the Package to be considered complete;
 4. Notify the Applicant that a submitted Plat Package is incomplete within the time constraints and with the specificity required by these Regulations, and determine whether subsequent submissions of documents and/or information make the Plat Package Submission complete within the period provided in these Regulations;
 5. Notify the Applicant of the decision of the Commissioners Court within the time and with the specificity required by these Regulations;
 6. Receive all responses of the Applicant to notifications sent to the Applicant by the Director of Engineering's Office;
 7. Reply to any Applicant Response received, determine whether the Applicant Response resolves the reasons for disapproval or condition(s) on approval, and notify the Applicant of their determination (which determination is delegated and assigned to the Director of Engineering by the Commissioners Court);
 8. Approve an extension of time requested by the Applicant;
 9. Approve revisions to a Final Plat previously approved by the Collin County Commissioners Court to accommodate unforeseen conditions arising during final design and construction;
 10. Release Bonds or other Financial Guarantees of performance after inspection and determination that the work is compliant or after the expiration of the warranty period. Performance bonds are not released until the expiration of the warranty period if the bond is also written to cover maintenance during the warranty period, but if not so written, the Performance Bond is released when a Maintenance Bond is substituted;
 11. Give Warranty and Maintenance Bond notices and oversee the process of getting warranty work performed;
 12. Perform any other functions or determinations expressly delegated to the Director of Engineering in these Subdivision Regulations; and
 13. Take all other actions necessary to administer these Subdivision Regulations and to comply with applicable law relating to the platting process.
- H. Exceptions from Plat Requirements
1. The Applicant for a tract of land subject to these Regulations who divides the tract into 2 or more parts is exempt from the platting requirements of these Subdivision Regulations provided that no part of the land is intended or designed for the laying out of streets, roadways, alleys, squares, parks, or other parts of the tract intended by the owner of the tract to be dedicated to public use, and it meets one of the following conditions:
 - a. The Tract of land is to be used primarily for agricultural use, as defined by Section 1-d, Article VIII, Texas Constitution, or for farm, ranch, wildlife management, or timber production uses within the meaning of Section 1-d-1,

Article VIII, Texas Constitution;

- b. The Tract of land is divided into 4 or fewer parcels and each of these parcels is to be sold, given, or otherwise transferred to an individual who is related to the Owner within the third degree by consanguinity or affinity, as determined under Chapter 573, Government Code;
 - c. All the lots of the Subdivision are more than 10 acres in area, each;
 - d. All the lots of the Subdivision are sold to veterans through the Veterans' Land Board program;
 - e. The Tract of land belongs to the State or any state agency, board or commission, or owned by the permanent school fund or any other dedicated funds of the State;
 - f. The Owner of the Tract of land is a political subdivision of the State; the land is situated in a 100-yr floodplain; and the lots are sold to the adjoining landowners;
 - g. One new part of the Tract is to be retained by the Owner who does not lay out any streets, alleys, parks, squares or other parts, and the other new part is to be transferred to another person who will further subdivide the Tract, and will do so subject to the plat approval requirements of these Regulations [Note: This requires an actual intent to develop the transferred part and the County may require a concept plan to support this intent. It also requires that the transferred land is of a size that it may be further subdivided, with consideration given to OSSF lot size regulations];
 - h. All parts of the Tract are transferred to persons who owned an undivided interest in the Original Tract and a Plat is recorded before any further Development of any part of the Tract. This will generally involve a situation where several persons inherit or otherwise receive an undivided interest in land and thereafter obtain a partition judgment to specifically divide the land among them. The partition does not trigger these platting requirements, however, any further division of the separate Tracts created by the partition for Development must comply with these platting Regulations;
 - i. The acquisition or disposition of land by any federal or state agency, political subdivision of the State, municipality, or school district intended for or relating to right of way purposes;
 - j. The Tract of land is to be used solely for the financing of the construction of a building or for the refinancing of an existing building with no change in property ownership.
- 2. Land divisions that are initially exempt under this Section or Development on Tracts which were a part of a division that was initially exempt require approval under these Subdivision Regulations at the time that subdivision of the land, as defined herein, is proposed to occur or at the time that the intended Development on the Tract exceeds the nature of the particular exception.
 - 3. An exception under this section is available only when each resulting tract has frontage on an existing public road or an existing legally established private road.

Any division requiring the creation or extension of an access easement, private road, or public street to serve one or more resulting tracts shall require plat approval.

4. Exception from these Regulations does not exempt the Applicant from requirements arising under Collin County Rules for On-Site Sewage Facilities and/or Floodplain Management Regulations.

I. Process for Exceptions from Platting Requirements.

To avoid the misapplication of an exception which could result in the violation of these Regulations, an Owner may apply online for a formal determination exception status with the Director of Engineering. No fee is required. The Director of Engineering shall review the application and the reasoning provided therein and within 10 business days of receipt shall make their formal determination in writing, which shall be provided to the Owner electronically. If the determination is that an exception from these Subdivision Regulations does not apply, the Owner is required to plat the subdivision of land pursuant to the procedures in these Subdivision Regulations.

J. Version of Regulations Applicable

1. A Plat that has received approval prior to the effective date of this 2026 amendment to the Regulations, and has not expired, shall be subject to the Subdivision Regulations in effect prior to these Amended Regulations or as otherwise provided by state law.
2. A Plat Package that is pending at the time that this 2026 amendment to the Regulations is adopted by the Commissioners Court shall be subject to the Subdivision Regulations in effect immediately prior to these Regulations, and such Regulations are kept in effect for such purposes.
3. A Plat Package submitted after the effective date of this 2026 amendment to the Regulations is subject to these amended Regulations.

K. Required Permits

No OSSF Permit, Culvert Permit, nor other applicable required permit shall be issued for a lot in a Subdivision for which a Plat, if required, has not been approved.


L. Appendices Incorporated

The appendices to these Regulations are incorporated herein by reference and are hereby made a part of these Regulations.

M. Subdivision Development Process

The figures below are intended to serve as a general overview of the Subdivision Development Process.


Figure 1.01-1. Subdivision Development Process - Plat Review & Approval



Key timelines:

10 business days to deem complete · Plat decision within 30 days
 Conditions or disapproval reasons after court decision
 Staff reviews applicant response within 15 days · Applicant response up to 2 years

Figure 1.01-2. Subdivision Development Process – Construction & Acceptance for Maintenance



Key timelines:

2-year warranty & maintenance period · Commissioners Court acceptance concludes the process

1.02 DEFINITIONS

A. Definitions

For the purpose of these Regulations, the following terms, phrases, words and their derivations shall have the meaning given herein. Definitions not expressly prescribed herein are to be determined in accordance with customary usage in planning and engineering practice. The word “shall” is mandatory and the word “may” is permissive.

ALLEY – a minor public right of way or Private Roadway Easement that is used primarily for vehicular services access to the back or sides of property otherwise abutting on a Roadway.

AMENDING PLAT – has the meaning given in §232.011 of the Texas Local Government Code and is intended to correct errors or add clarification.

APPLICANT – a Subdivider or Developer who seeks approval of a proposed subdivision, including the Plat.

AS-BUILT PLANS – revised set of drawings submitted by the Applicant upon completion of construction of the Road and Drainage Infrastructure Improvements. They reflect changes made in the specifications and civil construction plans during the construction process, as agreed to by the Director of Engineering, and show the actual, built dimensions of Road and Drainage Infrastructure Improvements.

BASE FLOOD – the Flood having a 1 percent chance of being equaled or exceeded in any given year. Also, the Flood resulting from the 100-yr storm event.

BASE FLOOD ELEVATION (BFE) – the Water Surface Elevation resulting from any Flood in Collin County, including outside of SFHAs, that has a 1 percent chance of equaling or exceeding that level in any given year, also called the 100-yr storm event. The BFE is used to delineate the Base Flood in plan review. The BFE may be calculated by the Applicant’s Engineer or as shown on the FIRM and found in the accompanying FIS for Zones A, AE, or AH for Collin County. The BFE shall be in relation to the datum specified in the FIS for Collin County.

BEST MANAGEMENT PRACTICES – physical, structural or managerial procedures that decrease the potential for facilities to pollute downstream channels, lakes, and waterways.

BUSINESS DAY – the days of the week when County offices are normally open (excludes official holidays and weekends). Collin County holidays may be found online.

COLLECTOR ROADWAY – a Roadway serving 150 lots or more, including those outside the Subdivision (i.e., future phases or connected Subdivisions). Collector Roadways provide connectivity between Residential Roadways and existing County Roadways or future Thoroughfares.

COMMISSIONERS COURT – the Commissioners Court of Collin County.

COUNTY – Collin County, Texas.

COUNTY CLERK – the County Clerk of Collin County.

COUNTY JUDGE – the County Judge of Collin County.

COUNTY ROADWAY – a Public Roadway under the control and maintenance of the County.

DEDICATION – the appropriation of land, or an Easement therein, by an Owner, for

the use of the public and accepted for such use by or on the behalf of the public.

DEVELOPER – any person, partnership, firm association, corporation (or combination thereof), or any officer, agent, employee, servant or trustee thereof, who performs or participates in the performing of any act toward the Development of a Subdivision, within the intent, scope and purview of these Regulations.

DEVELOPMENT – all land modification activity, including grading or construction of buildings, Roadways, drainage, parking lots and/or other impervious structures or surfaces.

DIRECTOR OF ENGINEERING – where used in these Regulations, “Director of Engineering” shall mean the Collin County Director of Engineering and their authorized and/or appointed representatives.

DRAINAGE PLAN – a plan for handling stormwater affecting existing and proposed property and/or Roadways due to Development, including Water Surface Elevations, Floodplains, velocities, and mitigation measures. Drainage plans include all areas handling stormwater, including SFHAs. For purposes of Plat submission and approval, the Drainage Plan does not require the submission of construction plans, but does require the identification, description, general dimensions, purpose, and capacity of proposed drainage improvements, providing a general summary of how the stormwater is expected to be handled. After Plat approval, a Drainage Plan which includes construction documents and greater detail will be required.

EASEMENT – an area for restricted use on private property upon which a public or private utility/entity/ HOA or Lot Owner responsible for maintenance shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs or other improvements or growth which in any way endanger or interfere with the construction, maintenance and/or efficiency of its respective systems on or within any of these Easements.

ENGINEER – a person licensed under the provisions of the Texas Engineering Registration Act to practice the profession of engineering in the State of Texas.

ENTITLEMENT – rights conveyed by approvals from government bodies to develop a property.

EXISTING ROADWAYS – Roadways that have been constructed and are in place prior to the passage of these Regulations.

EXTRATERRITORIAL JURISDICTION (ETJ) – as defined in Local Government Code, Chapter 42.

FEMA – Federal Emergency Management Agency.

FINAL ACCEPTANCE – formal acceptance by order of the Collin County Commissioners Court, or where applicable, by the Director of Engineering.

FINAL PLAT – the official drawing or map (including all necessary survey drawings, notes, information, affidavits, Dedications, certifications, and/or acceptances as required by these Regulations) of any given Subdivision of land which is prepared from actual field measurements and staking of all identifiable points by a Surveyor or Engineer, with the Subdivision location referenced to a survey corner and with all boundaries, corners and curves of the land division sufficiently described so that they can be reproduced without additional information.

FINANCIAL GUARANTEE IN LIEU OF BOND – in lieu of a Performance Bond the Applicant may deposit cash with the County or an eligible letter of credit on which the Collin County Judge or their successors in office is the named beneficiary. The amount of security or the amount of the letter of credit shall be the estimated cost of construction of the Road and Drainage Infrastructure Improvements. A letter of credit must comply in all respects with Section 232.0045 of the Texas Local Government Code. *Any Letter of Credit must be payable on the demand of the County, and the County shall not be required to make any showing of Entitlement to payment except for presentation of the Letter of Credit or a copy thereof.*

FLOOD OR FLOODING – a general and temporary condition of partial or complete inundation of normally dry land areas from the overflow of inland waters or the unusual and rapid accumulation or runoff of surface waters from any source.

FLOOD INSURANCE RATE MAP (FIRM) – an official map of a Community, on which the Federal Emergency Management Agency has delineated both the SFHAs and the risk premium zones applicable to the Community.

FLOOD INSURANCE STUDY (FIS) – is the official report provided by FEMA. The report contains flood profiles, Water Surface Elevation of the Base Flood, as well as the FIRM.

FLOOD STUDY – an examination, evaluation and determination of flood hazards and corresponding Water Surface Elevations, Floodplains, and velocities. Flood studies, when used herein, are associated with analysis of regulated SFHAs.

FLOODPLAIN OR FLOOD-PRONE AREA – any land area susceptible to being inundated by water from any source (see definition of Flooding). For Plats and civil construction plans, a Floodplain is a plan view depiction of the extent of Flooding based on calculated Water Surface Elevations.

GRADE – the elevation of a surface of the ground or paving at a point where height is to be measured or the degree, of inclination of a surface.

HOMEOWNER'S ASSOCIATION – an organized, non-profit corporation with mandatory membership when property is purchased.

INFRASTRUCTURE – roads, streets, bridges, stormwater and drainage improvements, water, sewer, gas, and electric lines, pipes and facilities, and other civil works.

LOT OF RECORD – a divided or undivided Tract or parcel of land having frontage onto a Roadway and which is, or which in the future may be, offered for sale, conveyance, transfer or improvement; which is designated as a distinct and separate Tract; and which is identified by a lot number in a duly approved Plat which has been properly filed of record.

MAINTENANCE BOND – a surety bond given that protects against defects in materials or workmanship, and damage to or deterioration of the Subdivision Improvements, that occur before and during the Maintenance Period due to any cause and to ensure that the Subdivision Improvements remain serviceable and maintained during the Maintenance Period which is for a period of 2 years after Final Acceptance of the improvements as complete by the County Engineering Department (which is not the same as acceptance for maintenance). Collin County through its County Judge must be the obligee on the bond. The Maintenance Bond must be payable to the County Judge or their successors in office.

MANUFACTURED HOME RENTAL COMMUNITY, MANUFACTURED HOME SUBDIVISION – a plot or Tract of land that is separated into 2 or more spaces or lots that are rented, leased or offered for rent or lease, for the installation of manufactured homes for use and occupancy as residences. The Development of Manufactured Home Rental Communities and Subdivisions is regulated by the Collin County Regulations for Manufactured Home Rental Communities Infrastructure. Contact Collin County Engineering Department for additional information.

MINIMUM REQUIREMENTS – minimum acceptable requirements; such requirements may be modified by the Director of Engineering as may be necessary to protect the public health, safety, and welfare.

MINOR PLAT – a Plat that the Director of Engineering has the authority to approve without approval of the Commissioners Court; further described in these Regulations.

ORIGINAL TRACT – see Parent Tract.

OWNER – the Owner of the Parent Tract or Lot of Record subject to these Subdivision Requirements.

PARENT TRACT – the Original Tract of land owned prior to any proposed division.

PERFORMANCE BOND – a bond given to ensure the proper construction of the Road and Drainage Infrastructure Improvements in the amount of the estimated cost of construction. Collin County through its County Judge must be the obligee on the bond. The bond must be made payable to the Collin County Judge or their successors in office. The Bond must comply in all respects with Section 232.004 of the Texas Local Government Code.

PLAT – a survey of the land which identifies the boundaries of a Tract and any Easements, Floodplains, Roadways, Rights of Way, and a drawing or map depicting the division or Subdivision of land into lots, blocks, parcels, Tracts or other parts.

PLAT PACKAGE – the application required by the County, the Final Plat containing all information required by these Regulations, required ownership documentation, utility service documentation, OSSF review documentation when applicable, and any other item specifically required by these Regulations for plat review and approval. Engineering studies and technical reports associated with roadway, drainage, floodplain, utility, or construction design are not required components of an administratively complete Plat Package unless expressly required by state law.

PRIVATE ROADWAY – a Residential Roadway that is typically owned and/or maintained by an entity other than the County and that is generally intended to serve residents located thereon but not the public at large. The term “Private Roadway” shall be inclusive of Alleys if the Alleys are to be provided within the Subdivision.

PUBLIC INTEREST – an interest shared by residents of the County as a whole and may generally be the interests of the public under regulations relating to the public health, welfare, or safety.

PUBLIC ROADWAY – a public Right of Way, however designated, dedicated, or acquired which provides vehicular access to adjacent properties. The Public Roadway may or may not be maintained by Collin County.

RECORD PLAT – the Plat drawing which has been approved by the Commissioners Court, signed by the County Judge and recorded at the County Clerk’s office.

RECREATIONAL VEHICLE PARK – a tract or parcel of land upon which two or more spaces are provided, leased, rented, or offered for occupancy by recreational vehicles for residential, transient, or extended-stay use.

REGULATIONS – Collin County Subdivision Regulations, as may be amended.

REPLATTING (or REPLAT) – the Re-Subdivision of any part of a block or lot of a previously platted Subdivision, or addition.

RESIDENTIAL ROADWAY – a Roadway serving less than 150 lots, including those outside the Subdivision (i.e., future phases or connected Subdivisions). Residential Roadways provide connectivity between residential driveways and Collector Roadways, existing County Roads, or future Thoroughfares.

RESIDUE TRACT – any part of the Original Tract remaining after its division.

RE-SUBDIVISION – the division of an existing Subdivision together with any change of lot size therein, or with relocation of street lines, or with the combination of lots or property adjacent to the existing Subdivision, or combination or division of lots within the existing Subdivision.

RIGHT OF WAY – a parcel of land that is occupied or intended to be occupied, by a Roadway or Alley. Where appropriate, “Right of Way” may include other facilities and/or utilities such as railroad crossings; and/or electrical, telecommunication, oil, gas, water, sanitary sewer and/or storm sewer facilities. The term “Right of Way” shall also include parkways and medians which are located outside of the actual pavement. The usage of the term “Right of Way” for land platting purposes shall mean that every public Right of Way hereafter established and shown on a Plat is to be separate and distinct from the lots or parcels adjoining such Right of Way and shall not be included within the dimensions or areas of such lots or parcels. The Right of Way is the distance between property lines measured at right angles to the centerline of the Roadway or Alley.

RURAL – a Subdivision having lots that are 1 acre or larger.

ROAD AND DRAINAGE INFRASTRUCTURE IMPROVEMENTS – roads, streets, alleys, bridges, ditches, stormwater control and drainage improvements and facilities, and items associated therewith.

ROADWAY – a paved Right of Way (or Easement), whether public or private and however designated, which provides vehicular access to adjacent land and/or connection to other Roadways or highways.

SETBACK LINE (BUILDING LINE) – a line established, in general, parallel to the Roadway Right of Way or Easement line. No building may be permitted in the area between the Setback Line and the Roadway Right of Way or Easement.

SINGLE-FAMILY RENTAL DEVELOPMENT – a development consisting of two or more detached single-family residential dwelling units located on a single tract or multiple tracts under common ownership that are intended primarily for lease or rental occupancy rather than individual fee-simple sale.

SPECIAL FLOOD HAZARD AREA (SFHA) – the land in the Floodplain subject to a 1 percent or greater chance of Flooding in any given year. Areas of special flood hazard are depicted on the Collin County FIRM as Zones A, AO, AH, or AE.

SUBDIVIDER – any person or agent thereof who is dividing or proposing to divide land

so as to constitute a Subdivision as that term is herein defined. The term “Subdivider” shall be restricted to include only the Owner, equitable Owner or authorized agent of such Owner or equitable Owner (such as Developer) of land that is sought to be subdivided through the Application process described herein.

SUBDIVISION – the division of a Tract of land situated within Collin County and outside the corporate limits of any municipality into 2 or more lots, parcels or Tracts for the purpose of sale or Development, or for the purpose of laying out Roadways, Alleys, squares, parks, public utility easements, public Rights of Way, private ingress/egress easements, drainage or stormwater improvements, or other parts of the Tract intended to be dedicated for public use or for the use of purchasers or owners of lots or parcels fronting on or adjacent to such facilities. The term “Subdivision” includes the term “addition”.

- a. A Subdivision of a Tract under this subsection includes a division regardless of whether it is made by using a metes and bounds description in a deed of conveyance, or in a contract for deed or sale or other executory contract to convey, or in a lease (other than agricultural or hunting leases), or by using any other method of conveyance of an interest of land.
- b. It is the intent of the Commissioners Court that the term “Subdivision” be interpreted to include all divisions of land, including divisions intended to create gated (i.e., Private Roadways) communities, that are not exempt under Section 1.01 H of these Regulations, to the fullest extent permitted under the laws of the State of Texas.
- c. For purposes of these Regulations, the term Subdivision includes the development of a Recreational Vehicle Park, and a Single-Family Rental Development or any similar development in which multiple residential units, spaces, or lease sites are created on a single tract for separate occupancy, regardless of whether individual lots are conveyed in fee simple. This provision does not include or require the platting of Manufactured Home Rental Communities, which are regulated under the Collin County Manufactured Home Rental Community Regulations.

SUBSTANDARD ROADWAY – a Roadway which does not meet the minimum Roadway standards described in the Collin County Roadway Standards.

SURVEYOR – a person licensed under the provisions of the Texas Professional Land Surveying Practices Act to practice the profession of surveying in the State of Texas.

TCEQ – Texas Commission on Environmental Quality.

THOROUGHFARE – a principal traffic artery, carrying higher volumes of traffic, more or less continuously, which is intended to connect remote parts of the area adjacent thereto and to act as a principal connecting Roadway with state highways.

TRACT – see Parent Tract.

URBAN – a Subdivision having lots that are less than 1 acre.

USABLE ACRE – a unit of area equal to at least 43,560 square feet. When calculating the usable acreage of any lot, the gross square footage within the lot shall be used, provided that any area that is dedicated for Right of Way purposes, within a Private Roadway Easement, an Easement for a shared access driveway, or any unusable

easements or areas as defined by TAC, Title 30, Chapter 285 regarding On-Site Sewage Facilities (OSSFs) shall be excluded.

UTILITY – water, sewer, gas, electrical, and/or any other utility services owned and/or operated by either a municipality, county, special district, or any other public, non-profit or private entity.

VARIANCE – a form of relief granted to an Applicant by the Commissioners Court on the basis of the criteria set out in these Regulations.

WATER SURFACE ELEVATION (WSEL) – the height in relation to the datum shown in the FIS for Collin County, of Floods of various magnitudes and frequencies.

1.03 PLAT PACKAGE SUBMISSION

A. Process Overview

1. Pre-submittal meeting (optional). Applicants will generally benefit from pre-submittal meetings, as once the Plat Package is submitted, staff will be concentrating on review and recommendation to the Commissioners Court. Matters discussed and worked-out in the pre-submission process may eliminate deficiencies that would otherwise be identified during the review and possibly become reasons for disapproval or conditions on approval by the Commissioners Court. Information provided for review as part of a pre-submission meeting does not constitute the submittal of a Plat Package. One or more pre-submission meetings may be held.
2. Submittal of Plat Package as defined in these Regulations is made by the Applicant along with the Application Fee.
3. Administrative completeness review by the Director of Engineering to determine the administrative completeness of the Plat Package submitted.
4. Within 30 days of receiving an administratively complete Plat Package, the Plat is brought before the Commissioners Court at a regular or special-called meeting for action.

B. Administrative Completeness

1. In order for a Plat Package submittal to be administratively complete, all information required for a Plat Package under these Regulations, or any list mandated by Chapter 232, Texas Local Government Code, must be submitted electronically to the Director of Engineering.
2. Engineering studies, including Traffic Impact Analyses, hydraulic analyses, flood studies, downstream assessments, and civil construction plans, shall not be required for determination of administrative completeness unless specifically required by state law for plat approval.
3. If the Director of Engineering determines that the Plat Package submittal is incomplete with reference to the requirements of these Regulations, the Applicant shall be notified within 10 Business Days of the date the Plat Package submittal was received with a written explanation of missing or required information or documents.
4. The Applicant shall be given a reasonable time to submit the missing information.

However, if the missing information is not received within 60 days of the notification to the Applicant of the missing information, the Plat Package may be administratively denied by the Engineering Department as incomplete, with notice in writing to the Applicant that the Plat Package has been administratively denied. The Applicant may, within 6 months thereafter, submit a Plat Package containing the missing information without having to pay a new application fee. Thereafter, a new application fee will be required.

5. The 30-day period for the Commissioners Court to act on the Plat does not begin until the Director of Engineering has received an administratively complete Plat Package.
6. A finding of administrative completeness is not an approval of the Plat Package.

C. Street Sign Plan

It is suggested that a Street Sign Plan be submitted at the same time as the Plat Package. A Street Sign Plan is not a requirement of Plat Package approval, however, both must be considered and acted upon by Commissioners Court. Concurrent submittal of these documents ensures both are placed on the Commissioners Court agenda for action on the same day. The Street Sign Plan must be signed and sealed by an Engineer and shall include street names, sign locations, and details for all proposed signs. If the street name signs are to be manufactured by someone other than Collin County, details for these signs shall be requested from the Collin County Engineering Department.

D. Application Fees

The Applicant shall pay a fee in the amount set by the Commissioners Court, with each submittal of a Plat Package. The fees are non-refundable except under the conditions set out in Section 232.0025 (i) of the Texas Local Government Code. Before the Plat can be filed for recordation, the Applicant shall pay 100% of third-party review fees, less the application fees previously paid, for all submittals reviewed in relation to the Development.

E. Final Plat Package Requirements

In order for a Final Plat package submittal to be administratively complete, each Final Plat Package shall be submitted electronically to the Director of Engineering and shall include the following information and materials:

1. A completed County online application submittal.
2. If Applicant is not the Owner, an Owner Authorization Form. See Appendix A.
3. The application fee.
4. Deed showing ownership of the property or properties being platted.
5. An original tax certificate showing that all taxes, currently due for the land being subdivided or Re-subdivided, have been paid. The certificate must be less than 30 days old when submitted.
6. The Plat containing all the required information specified in these Regulations.
7. An exhibit depicting all phases of the Development, proposed and future, shall accompany the Final Plat but is not required to be submitted with the Plat Package to be administratively complete. The exhibit shall show how the Roadways, Alleys

or Thoroughfares in the Development connect with adjacent land, adjacent recorded Subdivisions, and previously dedicated, Platted, and/or planned Roadways within 500 feet of the Subdivision. It shall show all surrounding Rights of Way within 500 feet of the proposed Development and include a table specifying the total number of lots, including those outside the Subdivision, contributing to each Roadway within the Subdivision. The total number of lots includes planned future phases of the subject Subdivision or planned interconnectivity with adjacent Subdivisions and may include plats or phases within a municipality.

8. If required by the Collin County Roadway Standards, a Traffic Impact Analysis may be submitted concurrently with the Plat Package but shall not be required for determination of administrative completeness or approval of the Plat. Any required Traffic Impact Analysis shall be reviewed and approved as part of the civil construction plan review process prior to commencement of construction.
9. Flood studies and other floodplain analyses may be submitted concurrently with the Plat Package but shall not be required for determination of administrative completeness or approval of the Plat. Any required floodplain analyses shall be submitted and approved as part of the civil construction plan review process and in accordance with the Collin County Floodplain Management Regulations prior to commencement of construction. If the Development is to be multi-phased, the study must include the areas where the future phases will be developed.
10. Drainage plans, hydraulic analyses, and related supporting documentation may be submitted concurrently with the Plat Package but shall not be required for determination of administrative completeness or approval of the Plat. Required drainage analyses and construction documents shall be submitted and approved as part of the civil construction plan review process and in accordance with the Collin County Drainage Design Standards prior to commencement of construction.
11. Utility provider will-serve letters signed and dated from the water, wastewater, and electric utility providers. The utility provider will-serve letter shall:
 - a. state that the provider has reviewed the utility plan, Easements, and Plat and can adequately serve the Development by meeting the State's minimum requirements;
 - b. state that the provider will inspect proposed utilities during construction; and
 - c. describe all bonding requirements;
 - d. Will-serve letters from water providers must include the water provider's certificate of convenience and necessity (CCN) number and indicate available flow. If available flow does not meet the minimum stated in the latest version of the International Fire Code adopted by Collin County, approval must be obtained from the Collin County Fire Marshal.
12. Where there is no existing facility or owner intending to construct and maintain the proposed water supply facilities, the developer may establish an investor-owned utility or create a municipal utility district and obtain a Certificate of

Convenience and Necessity (CCN) from the Public Utility Commission (PUC) and include evidence of the CCN issuance for the development area.

13. If groundwater under the land is proposed as the water source for the subdivision, a groundwater availability certification shall be submitted in lieu of a water provider will-serve letter. The certification shall be prepared, signed, and sealed by a licensed Professional Engineer or Geoscientist licensed to practice in Texas and shall verify that an adequate groundwater supply is available to serve the proposed development. The certification must also confirm that the proposed groundwater wells comply with all applicable permitting requirements of the North Texas Groundwater Conservation District (NTGCD) and the Texas Commission on Environmental Quality (TCEQ) for residential development. The certification shall be submitted directly to the NTGCD for review, with a copy and proof of submittal provided to the County.
14. If OSSF is proposed, approval of the OSSF Suitability Plat Review application from the Collin County Development Services Department.
15. Where there is no existing entity or owner to build or maintain the proposed wastewater treatment and collection facilities, the developer shall establish an investor-owned utility or a municipal utility district by obtaining a CCN from the PUC and include evidence of the CCN issuance for the development area.
16. If the Applicant will require subdivision covenants or they are required by these Regulations, a copy shall accompany the Final Plat but is not required to be submitted with the Plat Package to be administratively complete. The provisions in Section 1.04 E.6. will be required to be contained in any restrictive covenants.

F. Requirements For Final Plats

A Final Plat shall include the following:

1. General Information
 - a. The Plat shall be titled "Final Plat".
 - b. The Final Plat shall be submitted on 24" x 36" sheets.
 - c. North arrow, scale (both graphic and written) and date. The scale shall not exceed 1 inch = 200 feet, or as required by the Director of Engineering. Multiple sheets may be required on larger Subdivisions.
 - d. Name of the proposed Subdivision, which shall not be the same or similar to any other Subdivision within the County unless the Subdivision is an extension of a pre-existing, contiguous Subdivision.
 - e. A location map which shows the general location of the proposed Subdivision in relation to the County, other Subdivisions, major roads, towns, cities and/or topographical features.
 - f. Name, address and phone number of the property owner, the Applicant, and if applicable, the designated representative for the development group.
 - g. Name, signature, seal, date, address and phone number of the Surveyor and/or Engineer.
 - h. Name, address and phone number of all utility companies.

- i. A note stating the total acreage of the Subdivision (rounded to the nearest thousandth of an acre), the total number of lots within the proposed Subdivision, the smallest and largest lot size shown on the Plat, and the average lot size.
- j. The boundary lines and their relation to an original corner of the original survey, with bearings and distances, total acreage and legal description of the proposed Subdivision. The boundary line description of the Tract being subdivided shall close to an accuracy of one in ten thousand.
- k. Easements shall be dedicated by the Owner of a parcel of land to another person, public agency, the public, or a private corporation for specific and limited use of that parcel of land.
 - l. Recording information (volume and page deed reference or instrument number) of all existing Easements and all required offsite Easements.
- m. Description of monumentation used to mark all boundary, lot and block corners, as established by a Surveyor, and all points of curvature and tangency on Roadway Rights of Way.
- n. The date of preparation and any revision dates.
- 2. Lot, Roadway and Right of Way Information
 - a. Lot and block designations for each parcel.
 - b. Total acreage rounded to the nearest thousandth and dimensions of each lot.
 - c. The location of any lots and/or Easements proposed for cluster mailboxes, detention facilities, parks, squares, greenbelts, schools and/or other public use facilities.
 - d. Names of adjoining Subdivisions, property owner names, and the outline of the adjacent properties contiguous to the proposed Plat and for an area extending 200 feet from the property line of the proposed Plat, along with appropriate recording information (i.e., volume and page, deed reference, or instrument number).
 - e. Distance from the proposed Subdivision to the nearest roadway intersection in both directions along all roads adjacent to the Subdivision.
 - f. Name, location, length, and Right of Way or Easement widths of all proposed Roadways, proposed Alleys, and existing Roadways. Roadway names shall not conflict with existing Roadway names in an unincorporated area.
 - g. Location, size and proposed use of all proposed access easements or shared access driveways, if any.
 - h. Right of Way corner clips and sight visibility easements, as required by the Collin County Roadway Standards.
 - i. If applicable, dedication to the public of all Roadway Easements or Rights of Way.
 - j. Building and Setback Lines.
 - k. If applicable, the location and limits of a future transportation corridor identified pursuant to Section 201.619, Texas Transportation Code.
- 3. Drainage and Floodplain Information
 - a. The Plat shall be prepared in accordance with the requirements of the Collin

- County Drainage Design Standards and Floodplain Management Regulations.
- b. Easements as outlined in the Collin County Drainage Design Standards.
 - c. All SFHAs identified by the most current FIRM provided by FEMA with the community and panel number of the FIRM.
 - d. For Subdivisions not located within a SFHA, reference shall be made on the Plat that the Subdivision is not located within a SFHA and the community and panel number of the appropriate FIRM shall be included.
 - e. 100-yr Floodplains (FEMA SFHAs and non-FEMA) for all stormwater conveyance systems.
 - f. Delineation of any SFHAs being modified as a result of the proposed Development. Flood Study submittals shall follow the requirements in the Collin County Floodplain Management Regulations. If a LOMR is required, the LOMR shall be approved by FEMA prior to filing the Final Plat for recordation.
 - g. Dam breach inundation zones. If no jurisdictional dams affect this property, reference shall be made on the Plat stating this.
4. Water, Wastewater and Utility Information
- a. The location of all proposed utility easements, including sanitary control easements required by TCEQ for any public or private water wells.
 - b. Usable acreage per lot as it pertains to OSSF Regulations, if applicable.
5. Plat Notes and Certifications
- a. Certifications required as set forth in these Regulations (Surveyor, Owner, OSSF, final approval, etc.). Reference Appendix B.
 - b. Plat Notes as required in these Regulations. Reference Appendices C, D, and E.
- G. Amending Plat, Replat or Plat Revision, Minor Plat, Cancellation
1. Amending Plat
- An Amending Plat Package is subject to the same requirements as original Plats unless a requirement is deemed inapplicable to the Amending Plat by the Director of Engineering. The Director of Engineering is delegated the authority by the Commissioners Court to approve or deny and sign an Amending Plat on behalf of the Commissioners Court if the Amending Plat is signed by the Applicants and submitted for one or more of the following purposes:
- a. to correct an error in a course or distance shown on the preceding Plat;
 - b. to add a course or distance that was omitted on the preceding Plat;
 - c. to correct an error in a real property description shown on the preceding Plat;
 - d. to show the location or character of a monument that has been changed or that is shown incorrectly on the preceding Plat;
 - e. to correct any other type of clerical error or omission of the previously approved Plat, including lot numbers, acreage, street names, and identification of adjacent recorded Plats; or
 - f. to correct an error in courses and distances of lot lines between two adjacent lots if:
 - i. both lot owners join in the application for amending the Plat;
 - ii. neither lot is abolished;

- iii. the amendment does not attempt to remove recorded covenants or restrictions; and
- iv. the amendment does not have a material adverse effect on the property rights of the other owners of the property that is the subject of the Plat.

The amending Plat controls over the preceding Plat without the vacation, revision, or cancellation of the preceding Plat. Public notice, a public hearing, and the approval of other lot owners are not required for the filing, recording, or approval of an Amending Plat.

2. Replat

The Owner of real property in a Tract that has been subdivided may apply to the Commissioners Court for permission to revise the recorded Plat. A Replat is not permitted if it would conflict with any deed restrictions applicable to the property. The Plat Package is subject to the same requirements as original Plats unless a requirement is deemed inapplicable to the Replat by the Director of Engineering.

a. Process Where a Public Interest or Public Property is Affected

If a park, school, road, public property, or the Public Interest would be affected by the proposed revision:

- i. the Commissioners Court shall publish a notice of the application in a newspaper of general circulation in the County—which includes identification of the time and place at which the Commissioners Court will meet to consider the Plat Package and hear protests to the revision of the Plat;
- ii. the notice must be published 3 times during the period that begins on the 30th day and ends on the 7th day before the meeting;
- iii. except where the Replat only combines existing tracts (lots), if all or part of the subdivided lots have been sold to non-developer owners, notice must also be given by certified or registered mail, return receipt requested, at each Owner's address.

b. Process Where Public Interest or Public Property is not Affected

If the Commissioners Court determines that the revision to the Plat does not affect a Public Interest or public property of any type, the foregoing notice requirements do not apply; rather, the following requirements apply:

- i. the Commissioners Court shall provide written notice to the owners of lots within 200 feet of the platted lot/lots to be revised, as indicated by the most recent appraisal district records;
- ii. the notice of the application must be continuously posted on the County's website for at least 30 days preceding the date of the meeting at which the Plat Package is to be considered.

c. Ruling

The Commissioners Court shall grant the Replat by order if:

- i. the revision will not interfere with the established rights of any Owner of another lot in the Subdivision; or
- ii. each Owner whose rights would be interfered with has agreed to the revision in writing.

- d. OSSF Review
Depending on the nature of the revision, the Replat may have to go through the OSSF Suitability Plat Review process.
- 3. Minor Plat
A Minor Plat Package is subject to the same requirements as Final Plats unless a requirement is deemed inapplicable to the Minor Plat by the Director of Engineering. The Director of Engineering is delegated the authority by the Commissioners Court to approve or deny and sign Minor Plats on behalf of the Commissioners Court. Minor Plats are defined as Plats that:
 - a. involve 4 or fewer lots fronting a Public Road with access to utilities and which does not require submission and approval of civil construction plans under these Regulations [this type of Plat must go through the OSSF review and approval process before it can be approved unless the lots will be served by sanitary sewer service]; or
 - b. are necessary to show a change to an Easement, an unopposed encroachment, unopposed changes in Building Lines, or similar such matters that do not justify the delay and expense of a Replat. [If any change in Usable Acreage result, the Plat may be required to go through the OSSF review and approval process].A plat shall not qualify as a Minor Plat if it:
 - a. Requires construction of public or private roads;
 - b. Requires storm drainage improvements, other than driveway culverts;
 - c. Requires utility extensions;
 - d. Requires floodplain modifications;
 - e. Creates an Recreational Vehicle Park, Single-Family Rental Development, or Manufactured Home Rental Community; or
 - f. Otherwise requires civil construction plans as determined by the County Engineer.
- 4. Cancellation of Plat
A Plat may be cancelled only in limited situations and in strict compliance with the procedures for cancellation contained in Chapter 232, Subchapter A of the Texas Local Government Code.

1.04 DECISIONS ON THE PLAT PACKAGE

A. Submission to the Commissioners Court and Post-Submission Process

1. Commissioners Court Action

Once a complete Plat Package and Application Fee is received, action must be taken on the Plat within 30 days by the Commissioners Court. The Director of Engineering must assure that the matter is included as an agenda item on a Commissioners Court meeting held within the 30-day period. The Director of Engineering shall give a recommendation to the Commissioners Court. The Commissioners Court may either approve the Plat, approve it with conditions, or disapprove it with reasons. Failure of the Commissioners Court to act on a Plat within the 30-day deadline results in the Plat being approved by operation of law. Notes on the 30-day period:

- a. the Applicant (not the County) can request one 30-day extension in writing, and the extension will be deemed granted if the Director of Engineering agrees to it in writing not more than 20 days after the Plat Package is received;
- b. if the County is required to undertake a takings impact assessment, the period for decision may be extended by an additional 30 days.

It is within the Director of Engineering's sole discretion as to whether to accept any corrections or updates to the Plat Package after the 30-day review period begins.

2. Notification to the Applicant of the Decision

The Director of Engineering shall notify the Applicant of the decision in writing. If the decision was conditional approval, the writing must specifically identify each of the conditions. If the decision was disapproval, the writing must specifically identify each of the reasons for disapproval.

For each condition or reason identified, the writing must:

- a. state how it is directly related to the requirements of Subchapter A of Chapter 232 of the Texas Local Government Code;
- b. cite the law, statute or order/ordinance provision that is the basis for the condition or reason; and
- c. not be arbitrary.

3. Applicant's Response

Chapter 232 of the Texas Local Government Code gives a disappointed Applicant the right to file a response to the conditions on approval or reasons for disapproval. The Applicant must file this response with the Director of Engineering's Office. The period during which a Plat approved with conditions or disapproved can be responded to by the Applicant is not clearly stated by the law, but in no circumstance may such period exceed 2 years from the date of filing a plat application. The purpose of the response is for the Applicant to show the Director of Engineering that they have corrected or met the conditions on approval or resolved the reasons for disapproval.

4. Notification/County's Reply

The Director of Engineering is delegated the authority by the Commissioners Court to make a determination on its behalf whether, in light of the response, the Applicant has met the conditions for approval or resolved the reasons for disapproval.

The Applicant must be given notice of the Director of Engineering's determination within 15 days of receipt of the Applicant's Response. If the Response does not meet the conditions on approval or resolve the reasons for disapproval, the Director of Engineering must send the Applicant a Reply as part of the notification. The Reply must state that the Plat is approved with conditions or disapproved and identify the conditions or reasons with the same specificity as the initial notification of the Commissioners Court decision, except that it cannot raise new conditions/reasons that were not part of the original notice. [Note: more than one Response may be received over time, and each time this procedure must be

followed].

If the Response meets the conditions on approval or resolves the reasons for disapproval, the Director of Engineering is required to approve the Plat.

If the Director of Engineering does not make the decision within 15 days of receipt of the Response the Plat is deemed approved by operation of law and the Director of Engineering shall approve the plat.

5. Litigation

In the event there is existing litigation between a plat applicant and the County relative to the development (or portion of the development) for which a Plat Package has been filed, nothing prohibits the County from seeking judicial remedies to abate County consideration of the Plat Package until final resolution of any such litigation.

B. Effect Of Approval

1. Approval of a Plat does not constitute approval of roadway design, drainage design, floodplain analysis, utility design, traffic studies, civil construction plans, or other engineering documents. Such approvals shall occur separately through the civil construction plan review process.
2. Plat approval does not constitute approval or acceptance of Infrastructure.
3. Approval of a Plat does not authorize any site grading, construction, or Development activities, but merely authorizes the Applicant to proceed with civil construction plan approval.
4. Approval does not constitute any acceptance by the County for maintenance of any Roadways. Acceptance for maintenance shall require a separate order of the Commissioners Court entered at a date after the warranty period, as described in these Regulations, has expired.
5. No construction of the Infrastructure may commence until the following have been completed:
 - a. civil construction plans have been approved by the Director of Engineering;
 - b. a preconstruction meeting is held between the Director of Engineering, the Applicant, and the Contractor;
 - c. Street Sign Plan has been approved by the Commissioners Court;
 - d. if groundwater under the land is to be the source of water for the subdivision, approval letters from NTGCD, TCEQ, and the PUC; and
 - e. the Applicant's election as to how to secure the completion of the Road and Drainage Infrastructure Improvements has been implemented either:
 - i. by the approved Plat being held by the Director of Engineering only to be released to the Applicant for recording once the Road and Drainage Infrastructure Improvements are accepted as complete by the County (and the Warranty and Maintenance Bond requirements are met); or
 - ii. the Applicant providing an acceptable Performance Bond or other acceptable Financial Guarantee in Lieu of Bond to the County.

C. Securing Completion of Road and Drainage Infrastructure Improvements

1. Standard Election---Withholding Recordation

The standard election of Applicants is to have the approved Plat withheld from recordation with the Collin County Clerk's Office by placing the approved Plat in trust with the Director of Engineering only to be released to the Applicant for recordation with the Collin County Clerk's Office upon the Director of Engineering finding that the Road and Drainage Infrastructure Improvements are complete and that the Warranty and Maintenance Bond requirements have been met. No lots may be sold until the Plat is recorded.

2. Financial Guarantee(s)

If the Applicant elects to secure the complete construction and installation with an acceptable Financial Guarantee (Performance Bond or Other Financial Guarantee in Lieu of Bond) certain requirements apply:

- a. The duration of the Performance Bond or other performance guarantee shall be 2 years starting from the date that the Plat is recorded in the Collin County Clerk's Office. If required improvements are not complete by the expiration date of the guarantee, the County may, but is not required to:
 - i. require cash payment by the Applicant or surety company for the cost to complete the work to be held as security for completion of the work;
 - ii. require a letter of credit for the cost to complete the work to be held as security for completion of the work;
 - iii. require an extension of the guarantee for a specific period of time; or
 - iv. declare a default under the guarantee and draw upon/make a claim against the guarantee to have the work completed by others. [If a Performance Bond is involved, the surety often opts to complete the work itself through others].
- b. The Applicant is responsible for providing the Performance Bond for the benefit of Collin County. Collin County, through its County Judge, must be the obligee on the bond. Generally, the Applicant is the Developer. In certain situations where the Applicant is not able to secure a Performance Bond in the amount, as described in part c below, or term required, the County may allow for the Applicant's prime contractor to provide the Performance Bond, which must be payable to the Collin County Judge or their successors in office. If this is allowed, only one bond will be accepted. The County will not accept a series of separate bonds from contractors or subcontractors on the project. The Performance Bond must be made by a prime contractor responsible for the complete Road and Drainage Infrastructure Improvements. The Director of Engineering makes all decisions regarding approval of Performance Bonds.
- c. The amount of the Performance Bond or other performance guarantee shall be based on an estimate of construction costs provided by a Professional Engineer registered in the State of Texas. The amount shall be sufficient to ensure satisfactory construction and installation of the Road and Drainage Infrastructure Improvements and must be approved by the Director of Engineering. Guarantees of performance must comply with Sections 232.004 and 232.045 of the Local Government Code where applicable.
- d. A Performance Bond must be issued by a surety authorized to write bonds in

the State of Texas. Both the form of the Performance Bond and the surety must be acceptable to the Director of Engineering.

- e. It is important to note that even if a Performance Bond or Other Financial Guarantee in Lieu of Bond is provided, no residential or commercial construction is allowed until the Road and Drainage Infrastructure Improvements are accepted as complete by the County and the Warranty and Maintenance Bond requirements are met. Any person who undertakes any residential or commercial construction on a lot before the Road and Drainage Infrastructure Improvements are accepted as complete by the County violates these Regulations and commits an offense hereunder. This restriction shall be included in the Restrictive Covenants for the Subdivision Development, and the Applicant, or its successors or assigns, shall ensure that this restriction is contained in any sale agreement for each lot.
- f. See Appendix G for a sample Performance Bond.

D. Compliance with Subdivision Rules

Plat Package submissions and the Development shown on the Plat shall comply with the Subdivision Rules set forth in these Regulations except where otherwise provided in the applicable provisions of Chapter 232 or 245 of the Texas Local Government Code.

E. Recording of Plat

1. The approved Plat must meet all requirements stated in these Regulations in order to be filed for recordation in the Official Public Records of Collin County, Texas. Likewise, it must comply with the County Clerk's requirements for filing and provide sufficient space for the Clerk to place the recording information.
2. Before the Plat can be filed for recordation, the Applicant shall pay 100% of third-party review fees, less the application fees previously paid, for all submittals reviewed in relation to the Development.
3. It is the Applicant's responsibility to file the Plat for recordation in the Official Public Records of Collin County, Texas. The Applicant shall pay all filing fees, review fees, and any publication/ mailing fees related to any public notices that were required.
4. Prior to filing for recordation, the Applicant shall provide electronic files (PDF and Shapefiles) of the As-Built Plans to the Collin County Engineering Department. GIS files shall include linework for all property boundaries, Right of Way, Easements, Roadways, signals, lighting, drainage, water, and sewer facilities. Files shall also indicate locations of all ponds and embankments greater than 6 feet in height. The GIS files shall be compatible with Collin County GIS Services.
5. An original tax certificate showing that all taxes currently due for the land being subdivided or Re-subdivided have been paid shall be provided at the time the Plat is filed for recordation. The certificate must be less than 30 days old.
6. If Subdivision Covenants are required, a copy shall be submitted to the Director of Engineering for review and approval prior to the Plat being filed for recordation. Once approved, the Subdivision Covenants shall be recorded when the Plat is

recorded. The following will be required to be contained in any restrictive covenants.

- a. If sewage disposal is by means of OSSFs, indication that the Owner of each lot shall be required to obtain an OSSF license from the Collin County Development Services Department.
 - b. All driveway culverts shall be installed in accordance with the policies of the Collin County Drainage Design Manual.
 - c. No residential or commercial building construction shall be allowed until the Road and Drainage Infrastructure Improvements for the Subdivision have been accepted as complete by the County, the required Warranty and Maintenance Bond have been provided, and required permits issued by Collin County Development Services have been obtained.
 - d. Collin County is not responsible for the maintenance and repair of any drainage improvements located outside of County maintained Rights of Way.
 - e. Drainage Easements shall be maintained by the property owner or Homeowner's Association.
 - f. Unless maintained by a Homeowner's Association, the owners of lots upon which drainage improvements are located or adjacent are responsible for the maintenance, repair, and/or reconstruction of the drainage improvements in drainage easements shown on the Plat, and all work must comply with the Collin County Drainage Design Standards.
 - g. Collin County is not responsible for the maintenance and repair of any cluster mailbox, including the landscaping and drainage of the lot or Easement containing the cluster mailbox.
 - h. Homeowner's Associations with maintenance funds are required if Private Roadways are proposed.
 - i. If Roadways are dedicated to the public, neither a lot Owner nor a subsequent lot Owner has any right to obstruct the Roadway, including by gate, fence, or otherwise.
 - j. Unless expressly permitted in the easement language, no construction or planting of trees or shrubs is allowed in any public utility easement, and a public utility has the right to remove any such obstructions located on the Easement. In no case shall any item obstruct sight visibility.
7. After the Plat is recorded, the Applicant shall provide a County Clerk stamped copy of the Plat to the Collin County Engineering Department.
- F. No New Road or Drainage Infrastructure Improvements
If no new Road and Drainage Infrastructure Improvements are proposed, the recording of the Plat ends the Subdivision process.
- G. Approval Expiration
Once a Plat has been approved, the Applicant has 2 years from the date of the approval to make progress towards the completion of the Infrastructure. If by that time no progress has been made towards completion of the Infrastructure, the Plat

expires and the approval is automatically rescinded. If the Applicant still wishes to pursue the Subdivision Development, the Applicant must start the platting process over and submit a new Plat Package in accordance with the Regulations in place at the date of the new submission. Once a Plat has been approved, the Plat may expire pursuant to Section 245.005 of the Texas Local Government Code, as amended.

1.05 SUBDIVISION RULES

A. Lots

1. Size

The size of lots is not set or addressed by these Regulations. [Note: OSSF Rules effectively establish a minimum size for lots dependent on OSSF Systems].

2. Easements

Sufficient room must be provided for public and private Easements such as Roadway, drainage, and utility easements. See the Collin County Roadway Standards and Drainage Design Standards for more information on Easement requirements.

3. Relation to Road

To the extent possible, lots should be laid-out so that side-lot lines are at a right angle to the fronted Roadway or radial to curved Roadway lines.

4. Lot Frontage on Existing County Roads

The minimum required lot frontage along existing County Roads is set at 100 feet. Proposed residential lots cannot front Thoroughfares identified on the Collin County Thoroughfare Plan unless approved by the Director of Engineering.

5. Setbacks

Minimum setbacks are as follows: 30 feet from the edge of Right of Way on all major highways and Thoroughfares; 20 feet from all other Public Roadway Rights of Way; and 25 feet from edge of pavement of all private roads. No building may be permitted within the setback.

6. Monuments

In all Subdivisions and additions, monuments shall be established at the corners of each block and lot in the Subdivision, consisting of an iron rod or pipe that is easily distinguishable from any other markers, set flush with the top of the ground.

B. Roadways

Roadways shall adhere to the Collin County Roadway Standards.

C. Drainage

Drainage improvements shall adhere to the Collin County Drainage Design Standards.

D. Floodplain

Development (public or private) in or adjacent to a Floodplain is subject to the Collin County Floodplain Management Regulations. Nothing in these Regulations shall be interpreted to relieve an Applicant from compliance with the Collin County Floodplain Management Regulations, and to the extent of conflict, the Collin County Floodplain Management Regulations control.

E. Design Requirements for Utilities

1. Fire hydrant spacing shall meet all requirements of the current International Fire Code that has been adopted by Collin County.
2. Utilities and their appurtenances shall be placed in dedicated utility easements or in the Right of Way if they are located in a manner that does not interfere with the maintenance of the Roadway and/or ditches, or any future expansion of the Roadway as shown on the Collin County Thoroughfare Plan.
3. Utility Easements shall be outside the design-yr Floodplain of the drainage conveyance systems.
4. Utilities placed within the 100-yr Floodplain shall meet all local, state, and federal requirements.
5. Refer to the Collin County Right of Way Use Policy and Collin County Floodplain Regulations for additional Utility placement requirements.
6. Unless expressly permitted in the easement language, no structures, walls or other obstructions shall be built over Utility Easements. In no case shall any item obstruct sight visibility.

F. Shared Access Driveways

1. Where adequate driveway spacing cannot be achieved to meet the regulations of the Texas Department of Transportation or Collin County, shared access driveways may be considered. Proposed shared access driveways shall be submitted to the Director of Engineering for consideration.
2. If shared access driveways are permitted, each of the lots sharing use of the shared access driveway shall hold equal, indivisible, irrevocable and unrestricted rights in the shared access driveway. These rights shall be established by a recorded Easement and the Easement shall run with the land of each of the benefited lots. The Easement instrument (Plat or separate instrument) shall clearly state each lot's pro rata responsibility with respect to future maintenance and/or repairs of the shared access driveway.

G. Mailboxes

1. Placement of mailboxes shall be in accordance with United States Postal Service (USPS) requirements and shall not interfere with regular maintenance of the roads and ditches.
2. Cluster mailbox systems shall be located within the Right of Way, an Easement, or a dedicated lot. Maintenance of the cluster mailbox area shall be specified in the restrictive covenants.
3. All mailboxes within County Rights of Way shall meet current TxDOT standards if the speed limit on the County Roadway is more than 40 miles per hour. Mailboxes in Subdivisions with speed limits at or below 40 miles per hour must meet USPS requirements and must be placed in a manner that does not interfere with the efficient movement of traffic or with visibility from driveways, intersecting Roadways or other access points.
4. Mailbox locations shall be approved by the USPS and/or TxDOT. Approval shall be provided prior to scheduling the preconstruction meeting.

H. Signs

1. All signs required by the Director of Engineering, including Roadway (street) name signs, regulatory signs (e.g., stop and yield), warning signs, and informational signs, must meet Collin County Standards and may be installed by the Applicant or County.
2. All signs shall be installed in accordance with the most current version of the "Texas Manual of Uniform Traffic Control Devices" (TxMUTCD).
3. For signs installed by the County, the County will prepare a quote for the signs and their installation. The Applicant shall pay the amount shown on the quote prior to installation.
4. If Roadway (street) name signs are provided by an outside source, the Applicant shall request details from the Collin County Engineering Department.
5. Monument signs at the entrances to Subdivisions shall be placed outside the Right of Way, unless approved by the Director of Engineering, and shall be maintained by the property Owner or the Homeowner's Association.

1.06 CONSTRUCTION PLAN SUBMISSION AND REVIEW

A. General

1. If the proposed Subdivision involves new Road and Drainage Infrastructure Improvements the Applicant is required to submit civil construction plans and other information regarding Infrastructure. For the protection of the public, this information may be required to include general plans or general dimensions and specifications for Infrastructure in addition to Road and Drainage Infrastructure Improvements.
2. All Construction Plan submissions must contain the information required in this Section 1.06.
3. All Construction Plan submissions must comply with the Subdivision Rules set forth in these Regulations except where otherwise provided in the applicable provisions of Chapter 232 of the Texas Local Government Code. In addition, they shall comply with the Collin County Drainage Design Standards, Roadway Standards, Floodplain Management Regulations (if applicable), and OSSF Regulations (if applicable).
4. Approval of the OSSF Suitability Plat Review application from the Collin County Development Services Department must have already occurred by this point.

B. General Civil Construction Plan Requirements

1. Submission

Civil construction plans shall be submitted electronically to the Director of Engineering for review and approval prior to the commencement of construction.

2. General Requirements

- a. All improvements shall be designed in accordance with the Collin County Drainage Design Standards, Floodplain Management Regulations, Roadway Standards, other agency regulations that are applicable, and the latest versions adopted by Collin County of the International Fire Code and the North

Central Texas Council of Governments (NCTCOG) specifications and standard details.

- b. All submitted items shall be 100% complete at the time of the submittal. Any incomplete components of a submittal shall result in the entire submittal being considered incomplete and shall be returned to the Applicant not reviewed.
- c. The complete civil construction plans, technical specifications for items not provided by NCTCOG, construction details, requested calculations, and a geotechnical report (as required) shall be submitted electronically to the Director of Engineering for review and approval.
- d. The civil construction plans shall be submitted on 24" x 36" sheets. Each sheet of the civil construction plans shall contain a title block, including space for the notation of revisions. This space is to be completed with each revision to the plan sheet and shall clearly note the nature of the revision and the date that the revision was made.
- e. Each civil construction plan sheet shall bear the seal and signature of the Engineer who prepared the plans. If standard details are included in the civil construction plan submittal and the Engineer does not wish to seal the detail sheets, the Engineer shall provide the following certification on the title sheet of the plans:

"The standard [County, City, NCTCOG, TxDOT, etc.] details specifically identified in this set of construction plans [or specifically included in these bidding/contract documents] have been selected by me or under my direct responsible supervision as being applicable to this project.

_____, P.E., Firm Registration # or P.E. # _____"

- f. If groundwater is to be the source of water for the Subdivision, an appropriate permit/approval shall be provided from the North Texas Groundwater Conservation District (NTGCD) and TCEQ for residential Development prior to approval of the Construction Plans.
- g. If a wastewater treatment is proposed, an approved permit to treat and/or dispose of wastes for the ultimate build-out of the development shall be provided from TCEQ and plans and specifications for the proposed wastewater collection and treatment facilities shall have been approved by all entities having jurisdiction over the proposed wastewater collection and treatment facilities prior to approval of the Construction Plans. Please note, if pump and haul operations will be proposed at any point, a pump and haul plan shall be provided to the Director of Engineering.
- h. The following additional items shall be reviewed and approved as part of the civil construction plan review process when required by applicable County standards:
 - i. Traffic Impact Analyses
 - ii. Drainage Studies

- iii. Flood Studies
- iv. Downstream Evaluations
- v. Hydraulic and Hydrologic Reports
- vi. Utility Design Reports
- vii. Geotechnical Reports

C. Civil Construction Plan Checklist

The following information is intended to assist the Applicant's Engineer in preparation of civil construction plans for review by the Director of Engineering. It is not intended to be an all-inclusive list of all required information or of all design requirements. Plans not meeting these requirements may be returned without a review and marked "Incomplete". An accompanying letter will identify what is missing.

1. Requirements for all Civil Construction Plan Sheets

- a. Title block with engineering firm information, registration number, Engineer's seal, sheet title, and page numbers clearly shown.
- b. A minimum of 2 benchmarks are required on all pertinent sheets.
- c. North Arrow and scale clearly shown on each plan sheet.
- d. Legend (relevant to each sheet) showing all special symbols, line types and hatches used.
- e. Property lines and Right of Way lines shown and labeled.
- f. Roadway names labeled on all existing, proposed, and future Roadways.
- g. Lot & block numbers and ownership information (if lots not owned by one entity) shown for all lots.
- h. Easements shown and labeled with filling data if applicable.
- i. Floodplains shown and labeled.
- j. Caution notes shown when working next to any existing utilities (public and franchise).

2. Order of sheets

- a. Cover Sheet.
- b. Plat.
- c. General Notes.
- d. Roadway Typical Section.
- e. Roadway Plan and Profile.
- f. Grading Plan.
- g. Erosion Control Plan.
- h. Drainage Area Maps.
- i. Hydraulic Calculations.
- j. Detention/Retention Design and Hydraulic Calculations.
- k. Closed Storm Sewer Systems (as applicable).
- l. Driveway Culvert Plan.
- m. Water Plan.
- n. Sanitary Sewer Plan. (as applicable)
- o. Franchise Utility Plans (as applicable).
- p. Illumination and Signage Plan.
- q. Traffic Control Plan (site specific).

- r. Roadway Cross Sections.
 - s. Construction Standards and Details.
- 3. General Notes
 - a. All notes included in Appendix G.
- 4. Roadway Typical Section
 - a. Roadway type as defined in the Collin County Roadway Standards.
 - b. Section dimensions tied to the roadway centerline.
 - c. Right of way width.
 - d. Pavement width.
 - e. Sidewalk locations (if any).
 - f. Pavement section including subgrade, materials with application rates, and depths.
- 5. Roadway Plan and Profile
 - a. Plan View
 - i. Note specifying who will own and maintain the proposed Roadways.
 - ii. A note referencing the site-specific geotechnical report, if required by the Collin County Roadway Standards. The geotechnical evaluation and pavement design, in accordance with the Collin County Roadway Standards, shall be submitted with the plans.
 - iii. Posted speed limit and design speed.
 - iv. Roadway centerline stationing at 100-foot intervals, PC's, PT's, and curve data labeled.
 - v. Intersection, driveway, and island curb radii labeled.
 - vi. Existing, proposed, and future Roadways and drives shown and labeled.
 - vii. Right of way corner clips and sight visibility Easements provided, in accordance with the Final Plat.
 - viii. Storm inlets identified with paving stations and top of curb elevations at center of inlet.
 - ix. Drainage clarified by flow arrows at crests, sags, ridges, intersections, and valley gutters.
 - x. Existing and proposed water and sanitary sewer Infrastructure shown and labeled, if applicable.
 - xi. Existing and proposed franchise utilities shown and labeled that cross the proposed Roadway.
 - b. Profile View
 - i. Existing ground line for center of Roadway shown and labeled.
 - ii. Proposed profile grade line shown for all Roadways, labeled at 100-foot station intervals.
 - iii. For Urban Roadways, show right and left top of curbs at intersections where split grade occurs.
 - iv. For Rural Roadways, show right and left ditch flowlines.
 - v. Vertical curve stationing and elevations including PVC, PVI, PVT, crest/sag location, curve length, algebraic grade difference, and "K" values shown.

- vi. Roadway grades shown to the nearest 0.01%. Max and min grades per Collin County Roadway Standards.
 - vii. "Compacted fill" callout/note provided for all areas of fill.
 - viii. Storm, water, sanitary sewer, and franchise utility crossings shown, labeled, and dimensioned.
6. Grading Plan, Erosion Control Plan, Drainage Area Maps, Hydraulic Calculations, Detention/Retention Design and Hydraulic Calculations, Closed Storm Sewer Systems, and Driveway Culvert Plan
- a. Refer to the Collin County Drainage Design Standards for requirements.
7. Water Plan
- a. Plan View
 - i. Specify who will own and maintain the water Infrastructure.
 - ii. Show and label all existing and proposed utilities.
 - iii. Show and label water line leading to fire sprinkler systems as "fire line" where applicable.
 - iv. Label size, type and pressure class for all proposed water mains.
 - v. Show location for all water services and meters.
 - vi. Show and label all Easements.
 - vii. Dimension location of all mains, services, meters, and spacing from other utilities.
 - viii. Curve data and stationing provided.
 - ix. Show and label all fire hydrants, valves, fittings, fire department connection locations, and back-flow preventors.
 - b. Profile View
 - i. Profile all water mains larger than 8 inches in diameter.
 - ii. Existing and proposed ground line at centerline of pipe shown and labeled.
 - iii. Label station and flowline elevations at 100-foot intervals, and for all fittings, laterals, and crossings.
 - iv. Indicate length, type/class, slope and size of all lines.
 - v. Label all Utility crossings and parallel sewer/storm lines.
 - vi. Indicate length, type and size of encasement needed.
8. Sanitary Sewer Plan (if applicable)
- a. Plan View
 - i. Specify who will own and maintain the sanitary sewer Infrastructure.
 - ii. Show and label all existing and proposed utilities.
 - iii. Dimension location of all mains from other utilities.
 - iv. Label line name, size, thickness, and type of all proposed sanitary sewer lines.
 - v. Stub-outs labeled with size, slope, length, and flowline elevations (if not profiled).
 - vi. Show and label all Easements.
 - vii. Show centerline stationing for sanitary sewer.
 - viii. Show and label all manholes and cleanouts with rim elevations.

- ix. Indicate type and size of encasement where needed.
 - x. Show flow direction arrows for sewer main.
 - xi. Label all sanitary sewer Infrastructure as either public or private.
- b. Profile View
- i. Profile shown for all mains.
 - ii. Existing and proposed ground line at centerline of pipe shown and labeled.
 - iii. Label station and flowline elevation information for all manholes, cleanouts, crossings, laterals.
 - iv. Manhole inflow and outflow elevations to be designed with a minimum of 0.1' drop.
 - v. Indicate the type and diameter for all manholes.
 - vi. Indicate length, type/class, slope and size of all sanitary sewer pipe between manholes.
 - vii. All Utility crossings and parallel storm lines shown in profile.
 - viii. Indicate length, type and size of encasement as needed.
9. Franchise Utility Plans (if applicable)
- a. Locations of all franchise utility Infrastructure if located within the Rights of Way or any dedicated access, maintenance, or drainage Easements.
 - b. Above ground franchise utility structures shall not be located within open channels or ditches.
10. Illumination and Signage Plan
- Illumination is not required.
- a. Show all stop signs, speed limit signs, and other traffic related signage locations.
 - b. Verification of fire hydrant placement (3-foot clear zone) relative to stop signs and illumination, if provided.
 - c. Details of sign faces including sizes, colors, graphics, and text.
 - d. Illumination locations, if proposed. Consideration should be given to the electrical layout from the utility company.
 - e. Illumination, if proposed, shall be located on the opposite side of the Roadway from stop signs.
11. Traffic Control Plan
- A site-specific Traffic Control Plan may be included in the construction plan set, but at a minimum, shall be submitted for review and approval prior to the preconstruction meeting being scheduled. See section 1.07 C below for additional requirements.
- a. Design site specific traffic control plan.
 - b. Indicate posted speed limit or design speed.
 - c. Show all sign designations, graphics, and sizes.
 - d. Show channelization device type, locations, and spacing.
 - e. Show all traffic barricades and indicate type.
 - f. Show all detour routes and detour signage.
 - g. Show flagger locations where applicable.

- h. Show message boards with text for 2 phases.
- i. Show flashing arrow boards where applicable.

1.07 GENERAL CONSTRUCTION REQUIREMENTS

The requirements of this section are for the purpose of addressing the actual construction of the Infrastructure.

A. General

1. Unless otherwise noted in these Regulations or the Collin County Roadway Standards, all construction and materials shall conform to the most recently adopted version of the North Central Texas Council of Governments (NCTCOG) Public Works Construction Standards or to any other construction specifications adopted by the Collin County Commissioners Court. In the event an item is not covered, the Contractor shall bring the item to the attention of the Director of Engineering for approval or modification.
2. A preconstruction meeting with the Director of Engineering is required prior to the commencement of any work. The Contractor's Project Manager is required to attend.
3. Mixture designs for hot-mix asphalt or concrete pavement, or type and application rates for prime coat, surface coat, and fog seals, approved by the Applicant's Engineer, must be submitted to the Director of Engineering prior to beginning construction of the associated work.
4. Franchise utility plans, approved by the franchise utility companies, for franchise utilities proposed outside the Rights of Way, access/maintenance easements, and/or drainage easements, shall be provided prior to beginning construction.
5. Structurally designed construction details shall be provided for retaining walls greater than 3 feet tall. Construction of such walls cannot begin until a permit for this construction is obtained.
6. The Contractor shall provide the name, phone number, and email address of the Contractor's Project Manager to the Director of Engineering. The Contractor's Project Manager shall be on site or in daily communication with the project. The Director of Engineering shall be contacted if there is a change in any of the contact information for the Contractor's Project Manager.
7. The Applicant shall contact the Director of Engineering 48 hours prior to the commencement of any construction. Saturdays, Sundays, and holidays observed by Collin County shall not be considered as part of this notification.
8. A construction inspection fee based on the current fee schedule will be required prior to beginning construction. A reinspection fee will be required if initial inspection is failed.
9. The Director of Engineering shall inspect the construction of all Infrastructure in the Development during construction for compliance with the County's Regulations and specifications. The Applicant shall provide free access to the Development to the Director of Engineering. Inspection by Collin County, or a failure to inspect construction as required herein, shall not in any way impair or diminish the obligation of the Applicant to install improvements in the

Development in accordance with plans and specifications therefore as approved by Collin County and in accordance with the County's Regulations. Such inspections are not a representation that the work is compliant or free from defects. Neither the Applicant, the Applicant's Engineer, nor the Applicant's contractor shall be entitled to rely on such inspections and no liability to the inspector or the County may arise from such inspections. The Applicant, the Applicant's Engineer, and the Applicant's contractor shall rely solely on their own inspection and review although they are obligated to correct matters pointed out by the inspector.

10. Certified elevations (spot elevations) shall be submitted to the Director of Engineering as specified in the Collin County Roadway Standards and the Collin County Drainage Design Standards.
11. The Applicant is responsible for damages to existing paving, utilities, fences, etc., damaged by the construction of the proposed improvements. All damaged items shall be replaced to a condition equal to or better than its original condition. The Applicant shall make these repairs at the Applicant's own expense or reimburse for the actual cost thereof.
12. The Contractor shall take appropriate measures to prevent tracking of mud and/or soils onto existing and/or new pavement. Any tracking that occurs shall be removed immediately by the Contractor.
13. Drainage structures, swales, ditches, and detention facilities shall be clean and fully functional.

B. Construction Sequencing

1. All erosion control Best Management Practices (BMPs) shown in the Erosion Control Plan and/or the SWPPP shall be in place prior to commencement of any work.
2. The Contractor is responsible for complying with the requirements of the Texas Commission on Environmental Quality General Permit for Stormwater Discharges Associated with Construction Activities (TXR150000) (Construction General Permit).
3. Individual lots in a Subdivision are considered part of a larger common plan of Development, regardless of when construction activity takes place on that lot in relation to the other lots, and are required to have BMPs and comply with the Construction General Permit.
4. The Director of Engineering must be notified so that the initial installation of BMPs can be inspected prior to any earth disturbing activities.
5. Temporary stabilization measures must be installed within 14 calendar days of a temporary or permanent cessation of construction activity.
6. Detention/retention ponds, drainage easements, and vegetated open channels/swales shall be revegetated using solid sod and shall retain 100% vegetative coverage prior to final acceptance into the maintenance period. Roadside ditches and slopes steeper than 4H:1V shall be seeded and protected with erosion control mats. All other areas within the Subdivision shall be seeded

with evidence of germination and 100% coverage in order to be accepted into the maintenance period.

7. Construction sequencing shall adhere to the following:

- a. Install required site notices.
- b. Install and inspect perimeter BMPs, including construction entrances. The Director of Engineering shall perform an inspection of perimeter BMPs prior to continuation of work.
- c. Begin clearing and grubbing.
- d. Construct required detention ponds and temporary sediment basins and ensure they are fully functional.
- e. Construct ditches and other drainage features and associated BMPs to protect downstream properties before the remainder of construction is started.
- f. Install utilities and storm sewer systems, as applicable.
- g. Construct Roadways and ditches, as applicable.
- h. Place fog seal for 2-course surface treatment on Roadways.
- i. Seal joints for concrete Roadways.
- j. Install all signage.
- k. Final BMPs and vegetation installation.

C. Temporary Traffic Control

1. Temporary traffic control is required for work within County right of way.
2. Roadway closure requests must be submitted to the Collin County Public Works Department at least 48 hours prior to the desired closure time, exclusive of weekends and Collin County holidays.
3. Roadway closure requests must be submitted on the Collin County Road Closure Form.
4. All barricades, warning signs, lights, devices, etc., for the guidance and protection of traffic and pedestrians must conform to the installation shown in the current edition of TxDOT's Texas Manual of Uniform Traffic Control Devices (TMUTCD). Deviation from this standard must be approved by the Director of Engineering.
5. The Contractor shall be responsible for traffic control, warning and safety devices until all work has been accepted by as complete by Collin County.
6. When the normal function of the Roadway is suspended through closure of any portion of the Right of Way, temporary construction work zone traffic control devices shall be installed to effectively guide the motoring public through the area. Consideration for roadway user safety, worker safety, and the efficiency of roadway user flow is an integral element of every traffic control zone.
7. Traffic control plans shall be site specific and included either with the civil construction plans or as a submittal by the Contractor as determined by the County. All traffic control plans shall be prepared and submitted in accordance with the standards identified in the current edition of the TMUTCD.
8. All traffic control plans must be prepared by an Engineer or an individual that is certified in their preparation. Certification may be achieved through approved organizations such as International Municipal Signal Association (IMSA), American

Traffic Safety Services Association (ATSSA) or another recognized organization.

D. "Accepted" as Used Herein

The term accepted as used in this Section relates to acceptance of the construction as complete in accordance with the plans and specifications and being free of obvious material defects. Such does not mean acceptance by the County for maintenance.

E. Compliance with Subdivision Rules

Construction shall comply with the Subdivision Rules set forth in these Regulations except where otherwise provided in the applicable provisions of Chapter 232 of the Texas Local Government Code.

1.08 ACCEPTANCE OF CONSTRUCTION AS COMPLETE

A. "Accepted" as Used Herein

The term accepted or acceptance as used in this Section relates to acceptance of the construction as complete in accordance with the plans and specifications and being free of obvious material defects. Such does not mean acceptance by the County for maintenance unless it is explicitly stated.

B. Applicant or Contractor Request for Inspection

When the construction is believed to be complete in accordance with the County-approved plans and specifications, the Applicant, or the Applicant's contractor, may submit to the County Engineering Department in writing a request for inspection. The inspection should generally take place within 10 days after receipt of the request.

C. Post-Inspection

1. After completion of the inspection, the Director of Engineering shall make a determination as to whether the construction is complete in accordance with the County-approved plans and specifications and free of obvious defects. The Director of Engineering shall issue to the Applicant in writing one of the following:
 - a. Notice that the construction is approved as complete;
 - b. Notice that the construction is approved as complete to become effective on the performance of identified punch-list items (reinspection not required, the Applicant or contractor shall submit a report and photographs showing the completion of the correction work);
 - c. Notice of non-acceptance of the construction with an explanation of the deficiencies (a re-inspection is required for any corrective work).
2. Acceptance of construction as being complete is NOT acceptance for County maintenance purposes.
3. If the noted deficiencies are not corrected within a timeline set by the Director of Engineering, which shall not be less than 30 days, the Director of Engineering will send a demand in writing to the Applicant for the deficiencies to be corrected. If the Applicant fails to correct the deficiencies, the County will either refuse to release the approved Plat to the Applicant for recordation or, if applicable, draw upon or make demand upon the Applicant's performance guarantee (Performance Bond, Letter of Credit, cash deposit, etc.) to have the corrective work completed.

4. No applicable permits shall be issued until the Road and Drainage Infrastructure Improvements are accepted by the County as complete.
5. As a separate condition for acceptance of the Road and Drainage Infrastructure Improvements as complete, the Applicant must provide the Warranty and Maintenance Bond required by these Regulations.
6. As a separate condition for acceptance of the Road and Drainage Infrastructure Improvements as complete within a Special District, an Interlocal Agreement (ILA) must be approved and executed by the Commissioners Court for County enforcement of traffic regulations within the Special District.
7. On acceptance of the work as complete, the Applicant or the Applicant's contractor must provide digital files (PDF and Shapefiles) of the As-Built Plans for all projects. The GIS files shall include linework for property boundaries, Right of Way, Easements, Roadway, signals, lighting, drainage, water, and sewer facilities. Files shall also indicate locations of all ponds and embankments greater than 6 feet in height. The GIS files shall be compatible with Collin County GIS Services. The submission of the As-Built to the County Engineering Department as set out above is a condition of Plat recording.

1.09 WARRANTY AND SECURING MAINTENANCE OBLIGATION

A. Required For Acceptance As Complete

The Warranty and the Maintenance Bond described herein must be provided to the Director of Engineering as a condition of the issuance of a notice of acceptance of the Road and Drainage Infrastructure Improvements as complete. No determination of completion will be provided to the Applicant until the Warranty and Maintenance Bond are in place. See Appendix H for a sample Maintenance Bond and Appendix I for a sample warranty letter.

B. Nature Of Warranty

The Applicant shall provide or cause to be provided a warranty in favor of the County securing the completed work against defects in materials, workmanship, and including damage to or deterioration of the Subdivision Improvements, that occur before and during the Warranty Period due to any cause and to ensure that the Subdivision Improvements remain serviceable and maintained during such period.

C. Warranty Period

The warranty must begin when the civil construction is accepted as complete by the County and shall run for 2 years thereafter ("Warranty Period"). If a road is intended to be submitted to the County for acceptance of maintenance, no such acceptance can take place until after the Warranty Period has expired.

D. Bond For Maintenance During Warranty Period

1. The Applicant must provide a bond to secure the Applicant's obligation to provide or cause to be provided repairs and maintenance on the Road and Drainage Infrastructure Improvements during the Warranty Period for the benefit of the County. The Maintenance Bond must protect the County against defects in materials or workmanship, and including damage to or deterioration of the

Subdivision Improvements, that occur before and during the Warranty Period due to any cause and to ensure that the Road and Drainage Infrastructure Improvements remain serviceable and maintained during such period. If the Performance Bond in effect extends to cover such matters during the Warranty Period or is extended by the surety to provide such coverage, a new bond is not required. If not, the Applicant must provide or cause to be provided a Maintenance Bond with the County Judge or their successors in office being the named payee. The Maintenance Bond amount shall be equal to 100% of the cost of Roadways, signs, stormwater control improvements, drainage structures and all other construction of Road and Drainage Infrastructure Improvements.

2. The surety must be authorized to make surety bonds in Texas and must be acceptable to the Director of Engineering.
3. In some cases, as determined by the Director of Engineering, it may be necessary to allow the maintenance obligation to be secured by a Letter of Credit or other acceptable Financial Guarantee.
4. The Applicant is responsible to provide the Maintenance Bond for the benefit of Collin County. Generally, the Applicant is the Developer. In certain situations where the Applicant is not able to secure a Maintenance Bond in the amount or for the term required, the County may allow for the Applicant's prime contractor to provide the Maintenance Bond, which must be payable to the Collin County Judge or their successors in office. If this is allowed, only one bond will be accepted. The County will not accept a series of separate bonds from contractors or subcontractors on the project. Rather, the Maintenance Bond must be made by a prime contractor responsible for the complete Road and Drainage Infrastructure Improvements. The Director of Engineering makes all decisions regarding approval of Maintenance Bonds.

E. Maintenance During the Warranty Period

1. Preventative Maintenance

The best way for the Applicant and/or contractor to avoid liability under the warranty and to avoid bond claims is for the Road and Drainage Infrastructure Improvements to be properly maintained during the Warranty Period. If acceptance for County maintenance is desired, the County will not accept a defective or unmaintained Roadway.

2. Roadway Repairs

All pavement repairs shall be in accordance with the County's Roadway Standards. If repairs have been extensive, the Director of Engineering may require that before the Warranty Period expires, the Applicant provide or cause to be provided a one-course surface treatment for the full length and width of the Roadway to seal joints created by pavement repair and restore uniform appearance of the Roadway, depending on the extensiveness of the repairs and the appearance of the Roadway.

3. Geotechnical Review of Problem Areas

If sufficient road deficiencies, as determined by the Director of Engineering, are occurring beyond that which would be expected under the facts and

circumstances, the Director of Engineering, at the Applicant's cost, shall have core samples taken and a geotechnical report prepared to determine whether the Roadway was built to specifications and/or whether there are other factors at work, such as underground water. The Director of Engineering shall provide a copy of the report to the Applicant and contractor. A reasonable timeline shall be set for the Applicant to provide a plan for addressing the Roadway's deficiencies with the plan to be provided to the Director of Engineering. An additional warranty and warranty period shall be required for the remedial work upon completion of such work to resolve the Road's defects. The Applicant will reimburse the County for the cost of the geotechnical services within 30 days after receiving an invoice from the County for such costs. The geotechnical consultant's suggestions for repairing the Roadway shall be given due consideration.

4. Inspections

The Director of Engineering will conduct periodic inspections of the Road and Drainage Improvements and will notify the Applicant and contractor regarding any defects identified. If the defects are not cured within 30 days of the notice (or such longer period that has been granted in writing by the Director of Engineering), the County will resort to a claim on the Performance or Maintenance Bond, payment under the letter of credit, or application of monies on deposit to perform the corrective work or have it performed.

F. Provision For Maintenance of Drainage Improvements

1. Except for ditches that are adjacent to Roadways and/or culverts and other improvements that are a part of a Roadway accepted for maintenance by the County, the County generally will not accept drainage improvements for maintenance, including retention and detention ponds. Therefore, the Applicant must provide for this work to be done either by way of an HOA with a maintenance fund or by providing in the Deed Restrictions that each lot Owner is responsible for maintaining the portions of the drainage improvements on or adjacent to their lot.
2. If the growth of weeds and/or brush is allowed to materially diminish the ability of drainage improvements to handle stormwater, such is a public nuisance under Section 343.011(c)(11) of the Texas Health & Safety Code, and the County reserves the right to seek injunctive relief that the condition be abated or to undertake abatement of the public nuisance itself as provided for in the Health & Safety Code and assess the cost against the Owner(s) of the property, and, if necessary, place a lien upon the property for the cost of the abatement.

1.10 ACCEPTANCE OF ROADWAYS FOR COUNTY MAINTENANCE

A. Identified Defects and Deficiencies Must be Remedied

1. Inspection

Inspections will take place to determine whether the Roadways are to be accepted for County Maintenance.

2. All Defects and/or Deficiencies Must be Remedied

All defects and/or deficiencies must be remedied/corrected to the satisfaction of the Director of Engineering before the Roadway(s) will be accepted for County Maintenance. This includes remedying items noted regarding drainage Infrastructure.

3. Procedure

- a. After correction of all issues identified by the Director of Engineering, the Applicant shall file a written request for acceptance of the Roadways for County Maintenance with the Director of Engineering. The request must identify all Roadways made the subject of the request and include a location map showing the locations of the Roadways. The request must also identify the total linear feet of the road(s) for which the request is made by the Applicant. The Director of Engineering shall schedule the request for a Commissioners Court meeting for action by the Commissioners Court on the request. The Director of Engineering shall notify the Applicant of the date and time that the request will be considered. The Applicant is entitled to attend the meeting and be heard on the request.
- b. The Commissioners Court, in an open Commissioners Court meeting, votes whether to accept the Roadways for maintenance. A majority vote of those present and voting is required for acceptance. The request and the vote thereon shall be recorded in the Official Minutes of the Commissioners Court.
- c. If the vote is not to accept the Roadways for maintenance, the reasons for such determination shall be included in the motion preceding the vote. If the reasons are matters that can be corrected, the Applicant may, upon remedying those matters, submit a future request.

B. Roadways Not Eligible for County Maintenance

1. The County may only maintain Public Roads, so Private Roads are not eligible for County maintenance.
2. A Public Road for which no request for County maintenance has been submitted and approved is not eligible for County maintenance. If a request for maintenance is made at a later date, the road must be brought up to Collin County's Roadway Standards before it will be considered by the Commissioners Court.

1.11 PRIVATE ROADS

A. Compliance with these Subdivision Regulations

The purposes of these Regulations apply equally to Private Roads in a Subdivision. Therefore, Private Roads are subject to the same platting, construction plan review, election of how to secure performance, construction, inspection, acceptance (as complete) processes and requirements, and Warranty and Maintenance Bond requirements as a Public Road, and must be constructed to Collin County's Roadway Standards. If the County calls a bond due to substandard construction and/or insufficient maintenance of a private road, any subsequent repairs by the County shall not be deemed and does not constitute transfer of maintenance responsibilities to the County.

B. Bonds or Other Financial Assurances

To secure complete construction of the Infrastructure, the Applicant may elect to have the County withhold the recordation of the Final Plat until the County's acceptance of the roadway and drainage improvements as complete, or have the contractor provide a Performance Bond or other Financial Guarantee. Although the Applicant is the beneficiary of any Financial Guarantee, such Financial Guarantee must be submitted to the Director of Engineering for review and approval. This is to verify that the Applicant has adequately made provision for securing completion of the Private Road.

C. Plat Notes Regarding Private Roads

Where the Subdivision involves Private Roads, special Plat notes shall appear on or be appended to the Final Plat in addition to any other Plat Notes required by these Regulations. See Appendix D for required Private Road Plat notes.

D. Development Along Existing Private Roads

1. There are existing Private Roads in the County that were not originally built to Collin County Road Standards, and that may not have been maintained to a standard that will allow access by police, fire and emergency service agencies.
2. After adoption of these Regulations, no new Subdivision Development may take place along an existing Private Road unless the Private Road meets or exceeds the standard necessary to provide access to police, fire and emergency service agencies. This requires, at a minimum, a travelable causeway with an all-weather surface that is capable of supporting 75,000 pounds.
3. Any new roads proposed to connect to the Private Road must be built to the Collin County Road Standards.

1.12 VARIANCE

A. Criteria for Variances

1. The Commissioners Court shall have the authority to grant Variances from these Regulations when a special Public Interest and/or the requirements of justice demands relaxation of the requirements of these rules. The Director of Engineering is delegated the authority by the Commissioners Court to approve or deny design-related Variances on behalf of the Commissioners Court. Any Variance granted shall not have the effect of nullifying the intent and/or purpose of these Regulations. The conditions upon which the request for a Variance is based shall be unique to the property in question, and not generally applicable to other properties.
2. Factors to be considered in evaluating a request for Variance shall include:
 - a. Whether strict enforcement of the Regulations would deny the Applicant the privileges or safety of similarly situated properties with similarly timed Development;
 - b. The actual situation of the property in question in relation to neighboring or similar properties, such that no special privilege not enjoyed by other similarly situated properties may be granted;
 - c. That the granting of the Variance will not be detrimental to the public health,

safety and welfare, injurious to other property, and will not prevent the orderly Subdivision of the land in the area in accordance with these Regulations; and,

- d. Whether there are special circumstances or conditions affecting the land involved in the proposed Development such that strict application of these Regulations would deprive the Applicant of the responsible use of their land, or would result in undue hardship to the Applicant, through no fault of the Applicant.

B. Application Materials

Any person who wishes to apply for a Variance should apply in writing to the Director of Engineering with a list of any Variance(s) requested with detailed justification for each at the time of Plat Package submission.

C. Grant or Denial of Variance

1. The decision of the Commissioners Court or the Director of Engineering, if applicable, to grant or deny a Variance will be final.
2. Variances do not apply to OSSF Regulations or requirements of state or federal law.

1.13 ENFORCEMENT; PENALTIES; APPEALS; CONFLICT OF INTEREST; SEVERABILITY

A. Category of Offense

A person commits an offense if the person knowingly or intentionally violates a requirement of these Regulations, including the Roadway and drainage design and construction specifications incorporated into these Regulations, the rules of Collin County for OSSFs, and/or any appendices attached to these Regulations. An offense under this provision is a Class B misdemeanor (Section 232.005, Local Government Code).

B. Enforcement Actions

1. At the request of the Commissioners Court, the County Attorney, District Attorney or other attorney designated by the County may file an action in court of competent jurisdiction to:
 - a. Enjoin the violation or threatened violation of a requirement established by or adopted by the Commissioners Court under these Regulations; or
 - b. Recover damages in an amount adequate for the County to undertake any construction or other activity necessary to bring about compliance with a requirement established by or adopted by the Commissioners Court under these Regulations.

C. Enforcement of Plat Notes

The enforcement of Plat notes or restrictions is generally the responsibility of the Applicant and other persons holding property interests, whether in fee simple or by Easement, in the Subdivision.

D. Conflict of Interest

No member of the Commissioners Court shall participate in the decisions regarding a

Plat for property in which the person holds a “substantial interest” as that term is defined in Section 232.0048(b) and (c), Local Government Code. If a member of the Commissioners Court has a substantial interest in a subdivided Tract, the Commissioner shall file, before a vote or decision regarding the approval of a Plat for a Tract, an affidavit stating the nature and extent of the interest and shall abstain from further participation in the matter. Such affidavit must be filed with the County Clerk in accordance with Section 232.0048(d), Local Government Code.

E. Severability

In the event any article, appendix, section, paragraph, sentence, clause or phrase of these Regulations shall be declared unconstitutional or invalid by the valid judgment or decree of any court of competent jurisdiction for any reason, such declaration shall not affect any remaining part of these Regulations. It is the express intent of the Collin County Commissioners Court that the articles, appendices, sections, paragraphs, sentences, clauses or phrases of these Regulations be severable.

F. Amendment to Regulations

The Commissioners Court may amend these Regulations from time to time and may adopt new orders by vote of simple majority after a public hearing thereon is noticed and is held.

G. Appeal

In any instance under these Regulations where a decision is made by the Director of Engineering on the interpretation, application, or applicability of a regulation that is not the decision on the approval or disapproval of the Plat itself, that decision may be appealed to the Commissioners Court when the Applicant believes the decision to be improper, outside of the scope of these Regulations, or contrary to these Regulations or existing law. The appeal shall be requested in writing to the County Judge. The Commissioners Court will make a decision on the appeal within 30 days from the date of delivery of such written appeal request. [Note: This appeal process is not applicable to ultimate determinations on Plats, which have their own review process].

APPENDIX A OWNER AUTHORIZATION FORM

Owner's Authorization Form

Description of Property to be Subdivided:

Authorization.

I/we hereby certify that I/we am/are the owner(s) of the above described property. I/we am/are respectfully requesting processing and approval of a Plat Package for the subdivision of the Property. I/we hereby authorize _____ to sign the Plat Application and other necessary instruments on my/our behalf, and to act on my/our behalf during the processing and presentation of the Plat Package. _____ shall be the principal contact with the County in processing the Plat Package.

OWNER(S)

Signature

Printed Name: _____

Date: _____

Address: _____

Signature

Printed Name: _____

Date: _____

Address: _____

Signature

Printed Name: _____

Date: _____

[Continue with additional pages if necessary]

APPENDIX B CERTIFICATIONS

Unless the context clearly shows otherwise, the following Certifications must be on or appended to each Plat.

1. Owners Certificate [where there is a public dedication]

STATE OF TEXAS

COUNTY OF COLLIN

Whereas, _____(owners name) are the owners of a tract of land situated in the (name) Survey, Abstract No. (#), Collin County, Texas, and being out of a (#) acre tract conveyed to them by (name), and being more particularly described as follows:

(property description to be provided here)

NOW, THEREFORE, KNOW ALL MEN BY THESE PRESENTS:

That _____(owner name) acting herein by and through its duly authorized officers, does hereby certify and adopt this Plat designating the herein above described property as (Subdivision Name), an addition to Collin County, Texas and does hereby dedicate to the public use forever, the streets, rights-of-way, and other public improvements shown thereon. The (owner name) does herein certify the following:

1. The streets and alleys, if any, are dedicated in fee simple for street and alley purposes.
2. All public improvements and dedications are free and clear of all debt, liens, and/or encumbrances.
3. The easements and public use areas, as shown, and created by this Plat, are dedicated, for the public use forever, for the purposes indicated on this Plat.
4. No buildings, fences, trees, shrubs or other improvements or growths shall be constructed or placed upon, over or across the easements as shown, except that landscape improvements may be placed in landscape easements.
5. Utility easements may be used for the mutual use and accommodation of all public utilities desiring to use or using the same unless the easement limits the use to particular utilities, said use by public utilities being subordinate to the public's use thereof.
6. The public utilities shall have the right to remove and keep removed all or parts of any buildings, fences, trees, shrubs or other improvements or growths which may in any way endanger or interfere with the construction, maintenance, or efficiency of their respective systems in said easements.
7. The Public Utilities shall at all times have the full right of ingress and egress to or from their respective easement for the purpose of construction, reconstructing, inspecting, patrolling, maintaining, reading meters and adding to or removing all or parts of their

respective systems without the necessity at any time of procuring permission from anyone.

8. The owners of the lots adjacent to or upon which drainage easements are created by this Plat or the homeowner's association will be responsible for the maintenance and or the reconstruction of the drainage improvements constructed in said easements for the purpose of assuring the flow of storm water to the degree required by the design and original construction
9. Collin County will not be responsible for maintenance or repair of drainage improvements on private lots or adjacent thereto.
10. Collin County shall have the full right of ingress and egress to or from a drainage easement if necessary to maintain or repair the effect the drainage system in that easement is having on the use and maintenance of a roadway and the drainage systems of the roadway.
11. Roadways of the Subdivision are public roads and neither applicant or any future owner has the right to obstruct the Roadways by a fence, gate, or otherwise.
12. All modifications to this document shall be by means of plat and approved by Collin County.
13. This Plat is subject to the Subdivision Regulations of Collin County, Texas.

WITNESS, my hand, this the _____ day of _____, 20__.

BY:

Authorized signature.

Printed name and title.

SUBSCRIBED AND SWORN TO BEFORE ME THIS _____ day of _____, _____.

Notary Public, State of Texas

My commission expires: _____

2. OWNER CERTIFICATION--PRIVATE

STATE OF TEXAS
COUNTY OF COLLIN

Whereas, _____ (owners name) are the owners of a tract of land situated in the (name) Survey, Abstract No. (#), Collin County, Texas, and being out of a (#) acre tract conveyed to them by (name), and being more particularly described as follows:

(property description to be provided here)

NOW, THEREFORE, KNOW ALL MEN BY THESE PRESENTS:

That _____ (owner name) acting herein by and through its duly authorized officers, does hereby certify and adopt this Plat designating the herein above described property as (Subdivision Name), an addition to Collin County, Texas

The owner(s) of the property described above and wish to subdivide same into lot(s) and block(s), do hereby adopt this Plat attached hereto and titled "_____ to Collin County, Texas" as our legal subdivision of same and do hereby dedicate to the owners of the lots in said subdivision, public utilities serving said subdivision, emergency services providers with jurisdiction and public service agencies, the use of all the private streets and other easements shown hereon and do hereby grant an express easement across said private streets shown hereon for the use, benefit and accommodation of the County for any purpose related to the exercise of a governmental service or function, including, but not limited to emergency vehicle access, inspection services and code enforcement and for the mutual benefit, use and accommodation of all public utility entities. All streets shown hereon are private streets and are not dedicated for use as public streets or rights-of-way, and the public shall have no right to use any portion of such private streets. The sale of the lot(s) shown on this Plat shall be made subject to the restrictions and conditions recorded in the Official Public Records of Collin County

By filing this Plat of Record, owner(s) and all future owners by purchasing lots with reference to this Plat **acknowledge and covenant that Collin County is not accepting the Subdivision Roadways for maintenance and shall have no obligation to maintain or repair the Roadways in this Subdivision.**

That Utility easements may be used for the mutual use and accommodation of all public utilities desiring to use or using the same unless the easement limits the use to particular utilities.

That the public utilities shall have the right to remove and keep removed all or parts of any buildings, fences, trees, shrubs or other improvements or growths which may in any way

endanger or interfere with the construction, maintenance, or efficiency of their respective systems in said easements.

That the Public Utilities shall at all times have the full right of ingress and egress to or from their respective easement for the purpose of construction, reconstructing, inspecting, patrolling, maintaining, reading meters and adding to or removing all or parts of their respective systems without the necessity at any time of procuring permission from anyone.

That the owners of the lots adjacent to or upon which drainage easements are created by this Plat or the homeowner's association will be responsible for the maintenance and or the reconstruction of the drainage improvements constructed in said easements for the purpose of assuring the flow of storm water to the degree required by the design and original construction.

That Collin County will not be responsible for maintenance or repair of drainage improvements on private lots or adjacent thereto.

Collin County shall have the full right of ingress and egress to or from a drainage easement if necessary for emergency repair if the drainage system in that easement is causing flooding or damage downstream.

A homeowner's association will be created upon recordation of this Plat. Membership is mandatory for each lot owner. The homeowner's association shall be responsible for maintenance of the roads in this Subdivision in perpetuity with such maintenance to be funded by dues collected from members.

Roads will be maintained to such a standard that will allow access by police, fire, and emergency service agencies. This, at a minimum, requires a travelable causeway with an all-weather surface capable of supporting 85,000 pounds.

WITNESS, my hand, this the _____ day of _____, 20__.

BY:

Authorized signature.

Printed name and title.

SUBSCRIBED AND SWORN TO BEFORE ME THIS _____ day of _____, _____.

Notary Public, State of Texas

My commission expires: _____

3. SURVEYOR'S CERTIFICATION

I am a Registered Professional Land Surveyor licensed by the State of Texas. This Plat is a true and accurate representation of the property described and platted hereon as determined by an actual survey made on the ground under my direction and supervision.

The property ____ is ____ is not ____ is partially within the 100-year floodplain.

By: _____

Printed Name: _____

R.P.L.S. Number: _____

SUBSCRIBED AND SWORN TO BEFORE ME THIS ____ day of _____, _____.

Notary Public, State of Texas

My commission expires: _____

4. HEALTH DEPARTMENT CERTIFICATION

I, as a representative of Collin County Development Services, do hereby certify that the on-site sewage facilities described on this Plat conform to the applicable OSSF laws of the State of Texas, that site evaluations have been submitted representing the site conditions in the area in which on-site sewage facilities are planned to be used.

By: _____

Printed Name: _____

Designated Representative for Collin County Development Services

5. CERTIFICATION OF COLLIN COUNTY COMMISSIONERS COURT

I hereby certify that the attached and foregoing Final Plat of the “_____” to Collin County, Texas was approved by the vote of the Collin County Commissioners Court on the ____ day of _____, 20____ at a meeting held in accordance with the Texas Open Meetings Act. This approval does not create an obligation upon Collin County for the construction and/or maintenance of any roads or other improvements shown of the Final Plat.

COLLIN COUNTY JUDGE

6. CERTIFICATE OF DIRECTOR OF ENGINEERING OR DESIGNEE WHERE APPROVAL OF PLAT INSTRUMENT DELEGATED

CERTIFICATION OF COLLIN COUNTY, TEXAS

I, _____, as Director of Engineering (designee) have been delegated the authority to approve the foregoing _____ Plat on behalf of the Commissioners Court of Collin County, Texas. I hereby certify I exercised this authority on _____ to APPROVE the foregoing _____ Plat as the act and deed of the Collin County Commissioners Court. This approval does not create an obligation upon Collin County for the construction and/or maintenance of any roads or other improvements shown on the foregoing instrument.

Collin County Director of Engineering (or Designee)

SUBSCRIBED AND SWORN TO BEFORE ME THIS _____ day of _____, _____.

Notary Public, State of Texas

My commission expires: _____

APPENDIX C STANDARD PLAT NOTES

STANDARD PLAT NOTES:

1. Mailboxes shall meet USPS specifications.
2. Collin County is not responsible for the maintenance and repair of any cluster mailbox, including the landscaping and drainage of the lot or easement containing the cluster mailbox.
3. All roadway signs shall meet Collin County specifications.
4. Collin County will only maintain street signs and poles along public roads with materials currently approved and in use by Collin County Public Works.
5. Collin County will not be responsible for repairs or maintenance of private driveways.
6. Collin County will not be responsible for maintaining monument signs. Monument signs shall be maintained by the private property owner of the lot it is constructed on or by the Homeowner's Association.
7. Collin County does not, and will not, accept street lights for maintenance or operation.
8. A road dedicated to the public may not be obstructed, including by means of a gate.
9. No vertical objects with a height of more than 2 feet. shall be placed inside the Sight Visibility Easement. This includes fences, trees, shrubs, parked vehicles, mailboxes, above ground utility appurtenances, signs other than those necessary for traffic control and identification of roadway names, etc. Guard fence may be placed inside the Sight Visibility Easement provided the horizontal and vertical alignment of intersecting roadways allows an unobstructed view of oncoming traffic from the minor roadway over the guard fence/railing.
10. Blocking the flow of water, constructing improvements in drainage easements, and filling or obstruction of the floodway is prohibited.
11. The existing creeks or drainage channels traversing along or across the subdivision will remain as open channels and will be maintained by individual owners of the lot or lots that are traversed by or adjacent to the drainage course along or across said lots.
12. Collin County will not be responsible for the maintenance and operation of said drainage ways or for the control of erosion in said drainage ways.
13. Collin County will not be responsible for any damage, personal injury or loss of life or property occasioned by flooding or flooding conditions.
14. All surface drainage easements shall be kept clear of buildings, foundations, structures, plantings, and other obstructions to the operation, access and maintenance of the drainage facility.
15. The Owner of the detention facility lot shall be responsible for all maintenance of the detention facilities.
16. Fences and utility appurtenances may be placed within the 100-yr drainage easement provided they are placed outside the design-yr floodplains, as shown on the Plat.
17. All necessary Collin County authorizations (i.e. OSSF, floodplain permits, etc.) are required for building construction, on-site sewage facilities, and driveway culverts.
18. Driveway connections must meet Collin County specifications.

19. All private driveway tie-ins to a County maintained roadway, or roadway with expectations of being accepted into the County roadway network, must be even with the existing driving surface.
20. For residential lots smaller than 1 acre, finished pad elevations shall be no less than 12 inches above the top of curb adjacent to the pad.
21. For residential lots 1 acre or larger, finished pad elevations shall be 18 inches above all adjacent low spots.
22. Finished pad elevations shall be a minimum of 2 feet above the fully developed Base Flood Elevation when adjacent to 100-year floodplains.
23. Except for ditches that are adjacent to Roadways and/or culverts and other improvements that are a part of a Roadway, the County will not accept drainage improvements for maintenance, including retention and detention ponds. Therefore, the Applicant must provide for this work to be done either by way of an HOA; by providing in the Deed Restrictions that each lot owner is responsible for maintaining the portions of the drainage improvements on or adjacent to their lot; or other method.
24. Individual lots in a Subdivision are considered part of a larger common plan of development, regardless of when construction activity takes place on that lot in relation to the other lots, and are required to have BMP's and comply with the Construction General Permit.
25. The Developer, Contractor, or Builder of any structure on a single lot in a developing subdivision shall prepare an SW3P and submit to the Director of Engineering prior to receiving any permits.
26. Collin County will not accept sidewalks for maintenance.

APPENDIX D SPECIAL PLAT NOTES FOR PRIVATE ROADS AND SHARED ACCESS DRIVEWAYS

SPECIAL PLAT NOTES FOR PRIVATE ROADS:

1. Except as otherwise provided by Collin County's Subdivision Regulations, private roads proposed for this Subdivision must meet the Collin County Roadway Standards.
2. The roads in this Subdivision are private and will not be maintained by Collin County.
3. A homeowner's association will be created upon recordation of this Plat. Membership is mandatory for each lot owner. The homeowner's association shall be responsible for maintenance of the roads in this Subdivision in perpetuity with such maintenance to be funded by dues collected from members.
4. All deeds conveying lots in this Subdivision must contain notice to the grantee that all roads in the Subdivision are private and will not be maintained by Collin County, and that Collin County will not accept the roads for maintenance in the future.
5. Roads must be maintained to such a standard that will allow access by police, fire, and emergency service agencies. This, at a minimum, requires a travelable causeway with an all-weather surface capable of supporting 85,000 pounds.
6. Collin County is not responsible for traffic enforcement within the Subdivision.

SPECIAL PLAT NOTES FOR SHARED ACCESS DRIVEWAYS:

If shared access driveways are allowed:

1. Each of the lots sharing use of the shared access driveway shall hold equal, indivisible, irrevocable and unrestricted rights in the shared access driveway, which rights shall be established by a recorded easement and the easement shall run with the land of each of the benefited lots. The easement instrument (plat or separate instrument) shall clearly state each lot's pro rata responsibility with respect to future maintenance and/or repairs of the shared access driveway.

APPENDIX E STANDARD PLAT NOTES FOR SPECIAL DISTRICTS

STANDARD PLAT NOTES FOR SPECIAL DISTRICT:

1. Mailboxes shall meet USPS specifications.
2. Collin County is not responsible for the maintenance and repair of any cluster mailbox, including the landscaping and drainage of the lot or easement containing the cluster mailbox.
3. All roadway signs shall meet Collin County specifications.
4. Collin County will not be responsible for repairs or maintenance of private driveways.
5. Collin County will not be responsible for maintaining monument signs. Monument signs shall be maintained by the private property owner of the lot it is constructed on or by the Homeowner's Association.
6. Collin County does not, and will not, accept street lights for maintenance or operation.
7. A road dedicated to the public may not be obstructed, including by means of a gate.
8. No vertical objects with a height of more than 2 feet. shall be placed inside the Sight Visibility Easement. This includes fences, trees, shrubs, parked vehicles, mailboxes, above ground utility appurtenances, signs other than those necessary for traffic control and identification of roadway names, etc. Guard fence may be placed inside the Sight Visibility Easement provided the horizontal and vertical alignment of intersecting roadways allows an unobstructed view of oncoming traffic from the minor roadway over the guard fence/railing.
9. Blocking the flow of water, constructing improvements in drainage easements, and filling or obstruction of the floodway is prohibited.
10. The existing creeks or drainage channels traversing along or across the subdivision will remain as open channels and will be maintained by individual owners of the lot or lots that are traversed by or adjacent to the drainage course along or across said lots.
11. Collin County will not be responsible for the maintenance and operation of said drainage ways or for the control of erosion in said drainage ways.
12. Collin County will not be responsible for any damage, personal injury or loss of life or property occasioned by flooding or flooding conditions.
13. All surface drainage easements shall be kept clear of buildings, foundations, structures, plantings, and other obstructions to the operation, access and maintenance of the drainage facility.
14. The Owner of the detention facility lot shall be responsible for all maintenance of the detention facilities.
15. Fences and utility appurtenances may be placed within the 100-yr drainage easement provided they are placed outside the design-yr floodplains, as shown on the plat.
16. All necessary Collin County authorizations (i.e. OSSF, floodplain permits, etc.) are required for building construction, on-site sewage facilities, and driveway culverts.
17. Driveway connections must meet Collin County specifications
18. All private driveway tie-ins to a County maintained roadway, or roadway with

expectations of being accepted into the County roadway network, must be even with the existing driving surface.

19. For residential lots smaller than 1 acre, finished pad elevations shall be no less than 12 inches above the top of curb adjacent to the pad.
20. For residential lots 1 acre or larger, finished pad elevations shall be 18 inches above all adjacent low spots.
21. Finished pad elevations shall be a minimum of 2 feet above the fully developed Base Flood Elevations when adjacent to 100-yr floodplains.
22. Except for ditches that are adjacent to Roadways and/or culverts and other improvements that are a part of a Roadway, the County will not accept drainage improvements for maintenance, including retention and detention ponds. Therefore, the Applicant must provide for this work to be done either by way of an HOA; by providing in the Deed Restrictions that each lot owner is responsible for maintaining the portions of the drainage improvements on or adjacent to their lot; or other method.
23. Individual lots in a Subdivision are considered part of a larger common plan of development, regardless of when construction activity takes place on that lot in relation to the other lots, and are required to have BMP's and comply with the Construction General Permit.
24. The Developer, Contractor, or Builder of any structure on a single lot in a developing subdivision shall prepare an SW3P and submit to the Director of Engineering prior to receiving any permits.
25. Collin County will not accept sidewalks for maintenance.
26. The streets, including street signs, streetlights, sidewalks and mailboxes will be maintained by [inset name of Special District].
27. All parks and open spaces, common area lots, and retention or detention facilities will be maintained by [inset name of Special District].

APPENDIX F CONSTRUCTION PLAN NOTES

CONSTRUCTION PLAN NOTES:

A. GENERAL NOTES:

1. All construction shall conform to the North Central Texas Council of Governments Public Works Construction Standards, most recently adopted version, unless otherwise noted. In the event an item is not covered, the contractor shall bring the problem to the attention of the Engineer for approval or modification.
2. Existing paving, utilities, fences, etc., damaged by the construction of the proposed improvements shall be replaced to a condition equal to or better than its original condition. The Applicant shall make these repairs at their own expense.
3. The Applicant may be responsible for damages to existing County Roads. Collin County and the Contractor shall document the existing County roadway prior to and following construction.
4. Contractor shall maintain the integrity of existing County roadside ditches. The drainage plan shall include any existing County roadside ditch which borders the subdivision.
5. Contractor shall be responsible for traffic control, warning and safety devices until all work has been accepted by Collin County.
6. All barricades, warning signs, lights, devices, etc., for the guidance and protection of traffic and pedestrians must conform to the installation shown in the most current copy of Texas Manual of Uniform Traffic Control Devices as currently amended, Texas Department of Transportation, and the approved traffic control plan for the work being performed.

B. PAVING NOTES:

1. The subgrade shall be lime stabilized with hydrated lime in the amount determined by a lime series to a finished depth of 6 inches minimum for the stipulated width, plus 1 foot each side of the next pavement layer. PI shall not exceed 15. The soil shall be tested for sulfates.
2. Flexible base shall meet the requirements of NCTCOG Item 301.5 - Flexible Base (Crushed Stone), Grade 1. Crushed stone shall be produced and graded from oversize quarried aggregate that originates from a single, naturally occurring source. Crushed concrete is not allowed when the final surface is two-course surface treatment. The flexible base supplier shall be approved by the Director of Engineering.
3. Compaction reports are only valid for 72 hours. Compaction reports received on a Friday are valid until noon on the following Monday unless otherwise approved by the Director of Engineering. Testing performed before inclement weather may be required to be repeated at the County's discretion.
4. Utilities placed under any existing roadway and/or paved driveway shall require a permit and shall be installed by boring or tunneling unless otherwise approved. Open cutting or trenching of a Collin County roadway surface will require a fee in addition to the repair cost per Local Government Code 240.907. Only pipe diameters of 30" or greater will be

allowed to open cut a county roadway. Permits are required for any work within County right of way. Roadway patching and repair shall be in accordance with the Collin County Roadway Standards.

5. The surface course shall be as shown in the construction plans.
6. Concrete reinforcing steel shall be #3 re-bar placed on 18" centers each way or as shown in the pavement sections.
7. Prime coat is required on flexible base prior to placement of asphaltic surface materials.
8. Aggregate for two course surface treatment shall meet the following criteria:
 - a. 1st course shall be grade 3, no coating required.
 - b. 2nd course shall be grade 4, no coating required. If non-coated aggregates are used, a fog seal is required.
 - c. Aggregate and pre-coating shall be in accordance with the current TxDOT Standard Specifications for Construction of Highway, Streets and Bridges.

C. PRECONSTRUCTION SUBMITTALS REQUIRED:

The items in this section shall be submitted to the Director of Engineering prior to commencement of construction.

1. Embankment (Fill)
 - a. Gradation, Atterberg Limits, and Standard Proctor curves as determined by ASTM D-698 performed on bulk samples of all embankment materials to be used.
 - b. Embankment material must be tested and these test results must be submitted to the Director of Engineering before they are allowed.
2. Lime Stabilization
 - a. Results of lime series, sulfates testing, and Standard Proctor curves as determined by ASTM D-698 for all subgrade soils to be stabilized.
3. Flexible Base
 - a. Gradation, Atterberg Limits, and Modified Proctor curves as determined by ASTM D-1557 performed on bulk samples.
 - b. Certification that the flexible base is crushed stone.
4. Surface Treatments
 - a. Certifications and application rates for asphalt binders and aggregates to be used.
5. Hot-Mix Asphalt Concrete (HMAC)
 - a. Mixture design from the HMAC Supplier, certified by the Developer's Engineer.
6. Portland Cement Concrete
 - a. Mixture design from the Portland Cement Concrete Supplier. The Developer's Engineer shall certify that the mixture design is in accordance with the requirements of the Civil Construction Plans and Specifications.
 - b. Supplier mixture design verification shall have been performed within the prior 6 months of the submittal date of the mixture design.
 - c. Shop drawings of rebar layouts and material certifications.
7. Construction Inspection Fee

8. Retaining Walls

- a. Structurally designed construction details for retaining walls greater than 3' in height.

D. PHASES OF CONSTRUCTION; TESTING; INSPECTION:

The County will perform periodic inspections and Owner Verification Testing in accordance with the Collin County Subdivision Regulations and Roadway Standards. Applicant is responsible for coordinating and paying for all inspection and Owner Verification Testing. In the event an inspection or test fails 2 consecutive times, a re-inspection/re-test fee of \$200 will be charged and payment shall be received prior to a follow-up inspection or test.

Testing and submittal requirements shall follow those outlined in the Collin County Subdivision Regulations and Roadway Standards.

1. Director of Engineering shall be notified 48 hours prior to start of construction.
2. Director of Engineering shall be notified prior to starting each phase of construction.
3. SW3P- Perimeter BMP's shall be installed prior to removal of vegetation.
4. Detention Pond - Detention ponds shall be installed and fully functioning as detention ponds or temporary sedimentation basins prior to any other drainage infrastructure construction or development that diverts runoff off site. When not used as sedimentation basin, detention pond shall be sodded.
5. Roadway & Drainage- Roadway and ditch flow line shall be to grade w/ all culverts and utility crossings in place prior to lime application. All areas of fill shall be tested according to and must meet Collin County Roadway Standards.
6. Fill Areas- All areas to be filled for roadway construction and any ponds to be filled shall be compacted in loose lifts less than 8 inches to a minimum 95% standard proctor density, minus 2 to plus 4 percent of optimum moisture.
7. Subgrade- Subgrade shall be proof rolled, lime stabilized, and tested according to Collin County Roadway Standards and these Regulations. Test results are valid for 72 hours. Surface shall not be disturbed after testing. Unnecessary heavy vehicle traffic shall be avoided. Submit statement in writing from the Applicant's Engineer that finished subgrade and ditch flow lines meet plan specifications.
 - a. Tests for Plasticity Index of treated soils shall be done for every 2,500 CY of treated subgrade. A minimum of three (3) tests shall be performed for each roadway.
 - b. Tests for compacted lime stabilized subgrade density and moisture content shall be taken in accordance with Tex-115-E. Tests shall be performed at a frequency determined by the County on a case-by-case basis. Generally, density tests will be taken in a series of three, one at each edge of roadway and one closer to the centerline, every three hundred longitudinal feet, with a minimum of one test per lift. A minimum of 3 test series shall be performed for each roadway.
8. Base- Base shall be placed, proof rolled, and tested according to Collin County Roadway Standards and these Regulations. Test results are valid for 72 hours. Submit statement in writing from the Applicant's Engineer that finished base and ditch flowlines meet plan specifications.
 - a. Sampling and testing for gradation should be done for every 5,000 cubic yards of flexible base.

- b. Tests for compacted flexible base density and moisture content shall be taken in accordance with Tex-115-E. Tests shall be performed at a frequency determined by the County on a case-by-case basis. Generally, density tests will be taken in a series of three, one at each edge of roadway and one closer to the centerline, every three hundred longitudinal feet, with a minimum of one test per lift. A minimum of 3 test series shall be performed for each roadway.

9. Surface

- a. Two-course surface treatment - Flexible base shall receive prime coat within 72 hours of base approval. First course of surface treatment shall be applied within 48 hours of prime coat application. Integrity of base shall be maintained during paving process. Type of asphalt material and the application rates for each course shall be submitted to Director of Engineering for approval. The total gallons of asphalt applied to each roadway shall be submitted to the Director of Engineering for application verification.
- b. 2" HMAC - Flexible base shall receive prime coat within 24 hours of base approval. HMAC paving shall begin within 48 hours of prime coat application. Integrity of base shall be maintained during paving process.
 - i. Testing for in-place air voids shall be conducted by taking two (2) cores per 500 tons of asphalt placed, at least once per day of placement. A minimum of 25% of cores taken per day must be taken within 1-ft of the edge of compacted asphalt.
 - ii. Companion loose samples taken for in-place air voids shall be taken per 2,000 tons of asphalt placed, at least once per day of production.
- c. Concrete- Steel must be installed according to Collin County Roadway Standards and these Regulations and shall be inspected by the Director of Engineering prior to paving. Submit grade verifications after paving and final ditch work. Paving shall be complete within 72 hours of approved test.
 - i. At the point of concrete placement, four cylinders (2 at 7 days, 2 at 28 days) for each 50 CY per class, per day, for hand poured and 150 CY per class, per day for machine poured, shall be tested for compressive strength.
 - ii. For slump, entrained air and temperature of concrete, one test for each 50 CY per class, per day, for hand poured and 150 CY per class, per day for machine poured.
 - iii. Slump, entrained air, and temperature tests should be performed on the same load from which strength test specimens are made. Entrained air tests should only be performed when entrained air concrete is specified in civil plans.
- d. Areas with questionable drainage may be required to have additional ditch verification before final roadway acceptance.

10. Roadway and ditch flow line elevations shall be verified by the Applicant's Engineer at completion of subgrade, base, and final pavement as outlined in the Collin County Subdivision Regulations

E. EROSION CONTROL NOTES:

1. TCEQ site notice shall be on site and remain on site in a visible location until the requirements of the TCEQ Construction General Permit are established.
2. The contractor shall be responsible for Temporary Erosion, Sediment, and Water Pollution Control, per North Central Texas Council of Governments Public Works Construction Standards, most recently adopted version.
3. All erosion control measures shall conform to the Stormwater Pollution Prevention Plan and the Notice of Intent.
4. Applicant's SW3P and/or erosion control plan must include County ditches affected by the Subdivision.
5. Contractor shall take appropriate measures to prevent tracking of mud and /or soils onto existing and /or new pavement. Any tracking that occurs shall be removed immediately by the Contractor.
6. A construction entrance shall be located at an approved location on the plans and in a location which will not interfere with all phases of Roadway construction. The construction entrance shall remain in place until which time the Roadway is open for construction traffic.
7. Mud or debris from the construction entrance shall be removed from the Roadway daily.
8. A concrete wash out area shall be in an approved location and clearly noted on the plans. The wash out area shall be maintained until all required concrete construction is complete.
9. Contractor shall establish vegetation on all disturbed areas immediately after final grading.
10. Contractor shall maintain positive drainage throughout all phases of construction.
11. Inspections shall be performed according to the TCEQ Construction General Permit. Copies of the inspections shall be made available to Collin County within 24 hours upon request.
12. BMP's shall be maintained and replaced or removed as recommended by the required inspections.
13. All designed drainage easements outside of the roadway right of way, detention ponds in their entirety, and retention ponds from the normal pool elevation to the top of pond shall be sodded as soon as constructed and shall be fully vegetated prior to final acceptance into the 2-year warranty period and the filing of the plat.
14. All roadside ditches shall have erosion matting installed and seeded, sodded or hydro-mulched as soon as the roadway and ditch elevation verifications have been submitted and approved. Permanent perennial vegetation must be established, according to the Collin County Drainage Design Standards, prior to final acceptance into the 2-year warranty period and the filing of the plat.
15. All other disturbed areas shall be seeded, hydro-mulched or sodded with permanent vegetation (100% coverage) prior to acceptance. All vegetation must be in accordance with NCTCOG Item 204 - Landscaping.

F. GRADING PLAN NOTES:

1. Earthwork and stockpiles shall not interfere with or obstruct preconstruction drainage patterns until such time as on-site drainage improvements are constructed.
2. Ponds, outfalls, and ditch elevations shall be verified by the Applicant's Engineer as outlined in the Collin County Subdivision Regulations and Roadway Standards.
3. For residential lots smaller than 1 acre, finished pad elevations shall be no less than 12 inches above the top of curb adjacent to the pad.
4. For residential lots 1 acre or larger, finished pad elevations shall be 18 inches above all adjacent low spots.
5. Finished pad elevations shall be a minimum of 2 feet above the fully developed base flood elevations when adjacent to 100-year floodplains.
6. Fill Areas – All areas to be filled for roadway construction and any ponds to be filled shall be compacted in loose lifts less than 8 inches to a minimum 95% standard proctor density at moisture contents of minus 2 to plus 4 percent of optimum moisture.
7. Existing Pond Preparation
 - a. Prior to any construction in the pond area, the pond should be dewatered, preferably by means of pumping and diverting the water downstream of the pond area. Care should be taken so as not to create flooding or overtopping of any downstream structures or culverts.
 - b. Following dewatering, the bottom and sides should be excavated by the removal of the muck (soft soils) zone to the underlying stronger clays.
 - c. The excavated clay areas should then be compacted and proof rolled with a loaded dump truck, scraper, filled water truck, or similar pneumatic tire equipment to densify loose surficial soils and detect any further soft or loose zones or areas of weakness. The proof rolling should be performed in accordance with NCTCOG Item 203 - Site Preparation and Item 301.1 - Subgrade Preparation and observed by the Director of Engineering. Any soils failing proof roll testing should be undercut to firm soils.
 - d. Following the proof rolling operations, the surface soils should then be scarified to a depth of approximately 4 inches prior to placement of the first lift of compacted fill.
 - e. Fill material shall meet the requirements of the Collin County Roadway Standards and be compacted to 95% Standard Proctor Density at moisture contents of minus 2 to plus 4 percent of optimum moisture.

APPENDIX G SAMPLE PERFORMANCE BOND
Performance Bond for Subdivision Improvements

Date: _____

Bond No. _____

Penal Sum: \$ _____ (_____ and _____/100 U.S. Dollars)

Obligee:

Collin County, Texas

County Judge

Principal/Subdivider:

Surety:

Effective Date: On submission of the Performance Bond to the Collin County Engineering Department, being _____.

Start Date: On the date the Final Plat is Approved.

Expiration Date: On the date that is TWO (2) years after the date the Final Plat is recorded with the Collin County Clerk's Office. Said two years being described herein as the "Performance Period."

KNOWN BY ALL MEN THESE PRESENTS: That we, _____ ("Principal") as Principal, and _____ ("Surety") as Surety, are held and firmly bound unto Collin County, Texas ("Obligee") as Obligee, in the penal sum of

(_____ DOLLARS AND _____/CENTS) ("Penal Sum") for payment whereof the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents:

WHEREAS, Principal will construct, or cause to be constructed the Road and Drainage Infrastructure Improvements (as defined below) shown on the Final Plat and in the accompanying filings pursuant to the plans and specifications approved by the County for the _____ SUBDIVISION (the "Subdivision"), a final plat being on file with the Collin County Clerk, with such

construction to be completed within the Performance Period set forth above and free of defects that prevent acceptance by the County of the Subdivision Improvements as complete.

WHEREAS, this bond is issued pursuant to the County's Subdivision Regulations (as the same may be amended from time to time), and must be in the amount of 100% of the estimated construction costs of the Road and Drainage Infrastructure Improvements which are defined as: roads, streets, alleys, bridges, ditches, stormwater control and drainage improvements and facilities, and items associated therewith. The Road and Drainage Infrastructure Improvements are hereinafter referred to as "Subdivision Improvements".

WHEREAS, Principal and Surety firmly bind themselves to the obligation to construct the Subdivision Improvements in accordance with the County-approved plans and specifications within the Performance Period, free of defects that prevent acceptance by the County of the Subdivision Improvements as complete.

NOW THEREFORE, THE CONDITIONS OF THIS OBLIGATION ARE SUCH, that

If within the Performance Period the Principal shall faithfully complete the Subdivision Improvements in accordance with the County-approved plans and specifications, then this obligation shall be void; otherwise to remain in full force and effect. If the Principal fails in its obligation, on demand by the Obligor the Surety must: 1) within 30 calendar days after notice is issued by Obligor pay over to the Obligor the cost to complete the Subdivision Improvements in accordance with the County approved plans and specifications as determined by the Obligor's engineering estimate, and/or to repair or reconstruct any defective work preventing acceptance by the County of the Subdivision Improvements as complete as determined by the Obligor's engineering estimate; OR 2) Within 15 calendar days after notice is issued by Obligor, notify the Obligor in writing of its election to promptly commence and complete construction, re-construction, replacement, repair, or maintenance of the Subdivision Improvements pursuant to the County-approved construction plans and specifications for the Subdivision Improvements. The surety may not engage the Principal to complete the Subdivision Improvements without prior written consent of the Obligor, which consent may be withheld in the Obligor's sole discretion.

Unless a separate Maintenance Bond is Provided, this Bond shall extend to cover the 2-year warranty period required by the County's Subdivision Regulations and shall protect the Obligor against defects in materials or workmanship, including but not limited to damage to or deterioration of the Subdivision Improvements, that occur before and during the 2-year period following the County's acceptance of the Subdivision Improvements as complete, due to any cause and to ensure that the Subdivision Improvements remain serviceable and maintained during such period.

Surety for value received stipulates and agrees that no change, extension of time, alteration or addition of time for completion or the work to be performed, or the plans, specifications or drawings shall in any way affect its obligation on this Bond, and Surety does hereby waive notice of any such change, extension of time, or change to plans and specifications or to the work to be performed thereunder.

Any action under this Bond or arising out of the project covered by this Bond shall have as its sole, mandatory venue a court of competent jurisdiction in Collin County, Texas. Texas law shall govern.

Signed, sealed and dated this _____ day of _____, 20____.

Principal: _____

By: _____

Name: _____

Title: _____

Surety: _____

By: _____

Name: _____

Title: _____

ACKNOWLEDGMENT

Before me, the undersigned authority, on this day personally appeared _____, known to me to be the person whose name is subscribed on the foregoing instrument and acknowledged to me that they executed the same for the purposes and consideration therein expressed, in the capacity therein stated.

GIVEN UNDER MYHAND AND SEAL of the office this the ____ day of _____, 20____ A.D.

Notary Public in and for the State of Texas

ACKNOWLEDGMENT

Before me, the undersigned authority, on this day personally appeared _____, known to me to be the person whose name is subscribed on the foregoing instrument and acknowledged to me that they executed the same for the purposes and consideration therein expressed, in the capacity therein stated.

GIVEN UNDER MYHAND AND SEAL of the office this the ____ day of _____, 20____ A.D.

Notary Public in and for the State of Texas

APPENDIX H SAMPLE MAINTENANCE BOND

Maintenance Bond

Date: _____

Bond No. _____

Penal Sum: \$ _____ (_____ and _____/100 U.S. Dollars)

Obligee:

Collin County, Texas

County Judge

Principal/Subdivider:

Surety:

Start Date: Date of Final Acceptance as complete of the Road and Drainage Infrastructure Improvement(s) by the County Engineering Department Road. Acceptance Date: _____.

Expiration Date: On the date that is 2 years after the Acceptance Date of the completed Road and Drainage Infrastructure Improvement(s) (hereinafter "Subdivision Improvements"). Said two years being described herein as the "Maintenance Period."

KNOWN BY ALL MEN THESE PRESENTS: That we, _____ ("Principal") as Principal, and _____ ("Surety") as Surety, are held and firmly bound unto Collin County, Texas ("Obligee") as Obligee, in the penal sum of

(_____ DOLLARS AND _____/CENTS) ("Penal Sum") for payment whereof the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents:

WHEREAS, Principal has constructed, or caused to be constructed, and the County has approved the Subdivision Improvements (defined below) for the _____ SUBDIVISION (the "Subdivision").

WHEREAS, this bond is issued pursuant to the County's Subdivision Regulations (as the same may

be amended from time to time), and covers 100% of the construction costs for the Subdivision Improvements which consist of Road and Drainage Infrastructure Improvements for the Subdivision defined as roads, streets, alleys, bridges, ditches, stormwater control and drainage improvements and facilities, vegetative cover, and items associated therewith.

NOW THEREFORE, THE CONDITIONS OF THIS OBLIGATION ARE SUCH, that

1. The foregoing recitals and statements are each all true and correct.
If Principal shall maintain and keep in good repair the Subdivision Improvements, including maintenance and repair due to defects in materials, workmanship, and including damage to or deterioration of the Subdivision Improvements that occur before and during the Maintenance Period due to any cause, and further ensure that the Subdivision Improvements remain serviceable and maintained during for the 2-year Maintenance Period, this bond shall be null and void; otherwise this bond shall remain a valid and enforceable obligation of the Principal and the Surety. Generally, the Principal will be given notice and a 30-day cure period unless the time remaining on Maintenance Period does not allow for a 30-day cure period.
2. If the Principal defaults on its obligation hereunder, a notice of default will be sent to the Principal and the Surety. The Surety shall have the following options:
 - (a) Within 15 days of the date that notice of default is issued by the Obligee, agree to the Obligee doing or causing the work to be done, and pay the Obligee for such work in the amount of the engineer's cost estimate determined by the Obligee's engineer. The cost estimate is not required to exist at the time of the agreement. Once agreed, the engineered cost estimate will be determined.
 - (b) Pay the Obligee within 15 calendar days after notice of default is issued by the Obligee, the amount the Obligee deems necessary based on a general cost estimate including contingency as set forth in the default letter, to ensure that any or all of the Subdivision Improvements are performing and do not have defects in materials or workmanship, correct damage to or deterioration of the Subdivision Improvements, and take action to make the Subdivision Improvements serviceable and maintained. Such payment shall be paid to Obligee in Collin County, Texas, before 2:00 p.m. Central Standard Time on or before the 20th day after the date of such notice. Funds may be received by wire transfer, or
 - (c) Within 15 calendar days after notice of default is issued by Obligee, notify the Obligee in writing of its election to promptly commence and complete construction, re-construction, replacement, repair, or maintenance of the Subdivision Improvements pursuant to the County-approved construction plans for the Subdivision Improvements. The surety may not engage the Principal to complete the Subdivision Improvements without prior written consent of the Obligee, which consent may be withheld in the Obligee's sole discretion.

If the surety does not notify the Obligee of the option to be utilized within 15 calendar days after notice of default is issued by Obligee, Surety agrees that such shall constitute an election by Surety to pay the Obligee as provided in Section 2 (b) above.

Surety for value received stipulates and agrees that no change, extension of time, alteration or addition of time for completion or the work to be performed, or the plans, specifications or drawings shall in any way affect its obligation on this Bond, and Surety does hereby waive notice of any such change, extension

of time, or change to plans and specifications or to the work to be performed thereunder.

Any action under this Bond or arising out of the project covered by this Bond shall have as its sole, mandatory venue a court of competent jurisdiction in Collin County, Texas. Texas law shall govern.

Signed, sealed and dated this ____ day of _____, 20____.

Principal: _____

By: _____

Name: _____

Title: _____

Surety: _____

By: _____

Name: _____

Title: _____

ACKNOWLEDGMENT

Before me, the undersigned authority, on this day personally appeared _____, known to me to be the person whose name is subscribed on the foregoing instrument and acknowledged to me that they executed the same for the purposes and consideration therein expressed, in the capacity therein stated.

GIVEN UNDER MYHAND AND SEAL of the office this the ____ day of _____, 20____ A.D.

Notary Public in and for the State of Texas

ACKNOWLEDGMENT

Before me, the undersigned authority, on this day personally appeared _____, known to me to be the person whose name is subscribed on the foregoing instrument and acknowledged to me that they executed the same for the purposes and consideration therein expressed, in the capacity therein stated.

GIVEN UNDER MYHAND AND SEAL of the office this the ____ day of _____, 20____ A.D.

Notary Public in and for the State of Texas

APPENDIX I SAMPLE WARRANTY LETTER

Warranty for Maintenance of Subdivision Infrastructure Improvements

Applicant:

Beneficiary of Warranty: Collin County, Texas

Name of Development/Subdivision:

Subdivision Infrastructure Improvements:

Date of County Acceptance as Complete:

Warranty Period: a 2-year period starting on the date that the Subdivision Infrastructure Improvements are accepted as complete by Collin County.

Warranty:

In consideration of the County's acceptance of the Subdivision Infrastructure Improvements as complete and as required by the Collin County Subdivision Regulations, the Applicant warrants and guarantees the Subdivision Infrastructure Improvements against defects in materials, workmanship, and including damage to or deterioration of the Subdivision Infrastructure Improvements that occur before and during the Warranty Period due to any cause, and covenants and guarantees that Applicant shall ensure that the Subdivision Infrastructure Improvements remain serviceable and maintained during such period.

Enforcement: This warranty is a legal obligation of the Applicant and may be sued upon if the Applicant defaults in its obligations hereunder. The County may recover the engineering estimates of the amount of money necessary to do the needed work plus its attorney's fees and costs incurred therein. Texas law shall apply to any litigation arising under this warranty, and venue of any lawsuit shall be in a court of competent jurisdiction in Collin County, Texas.

APPLICANT: _____

By: _____

(signature)

Name: _____

(printed name)

Title: _____

ACKNOWLEDGMENT

Before me, the undersigned authority, on this day personally appeared _____, known to me to be the person whose name is subscribed on the foregoing instrument and acknowledged to me that they executed the same for the purposes and consideration therein expressed, in the capacity therein stated.

GIVEN UNDER MYHAND AND SEAL of the office this the ____ day of _____, 20____ A.D.

Notary Public in and for the State of Texas